

SCOPE OF WORK

Reference: P&IDs
Routing drawings
Piping Specifications
Insulation
Hangers & supports
Kinetics ASC Reno ESP E22-022, "Engineering Project
Documentation"

A. Bldg 330 – Non Sanitary Piping (Interior)

Start / End Date: May – Nov 2011

1. 0°C Glycol Loops (cost for 304L SS and carbon steel material) from chiller platform
2. Hot water distribution (from platform)
3. Chilled water distribution (from chillers platform)
4. City Water distribution (excluding restrooms).
5. Plant steam distribution and condensate traps
6. Vacuum distribution (cost for 304L SS and carbon steel material)

B. Bldg 330 Non Sanitary Piping (Exterior)

Start / End Date: July – Nov 2011

1. City Water distribution (4" line from corner of Bldg 315 to Bldg 330)
2. Plant steam distribution (3" line from corner of Bldg 315 to Bldg 330)
3. Cooling Tower Water (located on platform)