

**SCOPE OF WORK**  
**Bldg 330 - Sanitary Piping**

Reference: P&IDs  
Routing drawings  
Piping Specifications  
Sanitary Piping  
Insulation  
Pip Anchor  
Grifols ESP E22-022, "Engineering Project Documentation"  
Unit price sheet

**A. Bldg 330 – Sanitary Piping (Interior)**  
**Start / End Date: May - Nov 2011**

1. DI Loop (interior of Bldg 330)
2. HWFI Loop #1 (supply and return to HWFI storage tank T-4)
3. HWFI Loop #2 (from HWFI storage tank T-4 to CWFI heat exchanger skid and return to tank)
4. CWFI (VC) loop
5. CWFI (NVC) loop
6. Clean steam and condensate distribution
7. Compressed air distribution from filter station

**B. Bldg 330 – Sanitary Piping (Exterior)**  
**Start / End Date: July – Oct 2011**

1. HWFI loop from Bldg 300 storage tank T-2 to Bldg 330 tank T-4
2. DI Loop from Bldg 330 storage tank to Bldg 330 (exterior)
3. Clean Steam and condensate distribution from corner of Bldg 315 to Bldg 330 exterior
4. CCA distribution from corner of Bldg 315 to Bldg 330 Filter Station

**C. Unit piping costs per "Unit Price Sheet"**