ASC CONSTRUCTION MANAGEMENT COMPETITION RENO, NEVADA FEBRUARY 8 – FEBRUARY 11, 2006

REGION 7 RESIDENTIAL DIVISION PROBLEM

UCI EAST CAMPUS STUDENT APARTMENTS IRVINE, CALIFORNIA

CONTENTS:

SECTION 1 PROBLEM INSTRUCTIONS

SECTION 2A PHASING AND SCHEDULING

2B STAGING AND LOCISTICS

SECTION 3 ESTIMATING

SECTION 4 PLAN READING AND PROJECT ENGINEERING

(TO BE DISTRIBUTED LATER)

SECTION 1 PROBLEM INSTRUCTIONS

UCI East Campus Student Apartments Irvine, California

Problem Premise

Your team (Company) is a general contracting firm that has been selected to build this Project. The judges are the "Owners" of the Project. They will review your proposal (as outlined below) and will schedule an interview with your company.

1. Project Description

The project consists of four hundred eighty-eight (488) apartment units for the University of California, Irvine, Student Housing. It is made up of forty-two apartment buildings, five ancillary buildings and on-grade parking. Three of the ancillary buildings contain study rooms and laundry facilities for the students; one is a maintenance building. The fifth building is a recreation building which includes a pool and spa, fitness center, computer room and e-mail stations, multimedia conference center, state-of-the-art mini-theatre and game room. It also features an outdoor BBQ and fireplace, basketball and volleyball courts.

2. Proposal

The proposal consists of the following sections:

- A. Phasing and Scheduling
- B. Staging and Logistics
- C. Estimating
- D. Plan Reading and Project Engineering

Please make sure all forms are filled out completely and correctly and are turned in on time.

See individual sections for further instructions.

THE "OWNER UPGRADE" PORTION OF SECTION 3 MUST BE TURNED IN AT 8:30 PM; THE ENTIRE REMAINDER OF THE PROPOSAL MUST BE TURNED IN NO LATER THAN 11:00 P.M. THURSDAY, FEBRUARY 9, 2006.

NOTE: Ten percent (10%) will be deducted for proposals up to 10 minutes late. Proposals turned in more than 10 minutes late will receive no points. Only two (2) members from each team will be allowed at the problem turn-in session.

3. Oral Interviews

The oral interviews will begin Friday morning, February 10, and will proceed at approximately 30-minute intervals (schedule to be provided). Be prepared to give a sevento eight-minute oral presentation. The remaining time will be utilized for questions from the judges. The specific issues to be addressed in your presentation will be announced at a

later time. You should be prepared to answer questions about all aspects of the Project and your proposal.

Visual Aids/Oral Interview Presentation Material

All presentation materials for ALL teams must be turned in at 9:30 a.m. on Friday, February 10. Materials not turned in at this time (other than your personal notes, etc.) WILL NOT be allowed in the Oral Interviews. An easel and an overhead projector will be provided. Should any Company desire to use additional presentation tools such as a computer presentation using PowerPoint, the CD or other storage device containing the presentation must be submitted at the 9:30 a.m. Friday deadline. (This will be returned for your use at the time of your presentation.) In addition, your team must be able to set up your presentation in a two-minute period to allow adequate time for the interview.

4. Miscellaneous

- A. Question and Answer Period Question and answer sessions will be held at 9:30 a.m. and 2:00 p.m. on Thursday, February 9. At **least** one individual from each team <u>must</u> attend.
- B. <u>RFI's</u> All Requests for Information must be submitted on the form provided on Page 4. Answers to those questions that the judges feel are appropriate will be provided to all students in the form of addenda.
- C. <u>Oral Interview Schedules</u> At 9:30 a.m. on Friday, February 10, the schedule for the Oral Interviews will be determined by random drawing. At least one member from each team must be present.
- D. <u>Problem Recap Presentation</u> At 6:30 p.m. Friday, February 10, the judges will make a presentation on the actual project.

4. General

All answers are to be on forms provided in this booklet. Forms may be copied, but are not to be altered in any way.

All materials turned in to the judges must contain the SCHOOL NAME. The company or mascot name IS NOT SUFFICIENT.

Only ONE copy of each requested item is required. Do not submit your materials in binders, notebooks, etc. Submit only requested information. Only the staging plan and schedule will be returned to you for your presentations. If you will need a copy of any other sections for your presentation, be sure to keep one for your use.

5. Schedule Recap

Thursday, February 9

7:30 A.M. Problem Distribution

9:30 A.M. Question & Answer Session

2:00 P.M.

Question & Answer Session

8:30 P.M.

Turn in Owner-Upgrade Portion of Section 3

11:00 P.M.

Turn in Remainder of Problem

Friday, February 10

9:30 A.M.

Turn-in Presentation Materials /Draw for Orals

11:15 P.M.

Orals Begin

6:30 P.M.

Problem Recap Presentation

Remember...

- STAY ORGANIZED
- BE FLEXIBLE
- BE READY FOR LAST MINUTE CHANGES and
- HAVE FUN!



Oral Interviews

In your oral interviews with Morley Builders on February 10, your 8 minute presentation must cover each of the following items:

- Phasing, staging and logistics
- Section 3: Explain your recommended upgrades and your reasoning for choosing the specific upgrades over other options.
- Section 4, Question 9: Explain how you are going to approach and deal with the situation
- Section 4, Question 20: Explain how and why you would deal with this situation



REQUEST FOR INFORMATION

RFI No.:TIME SUBMITTED: PROJECT: UCI East Campus Student Apartments SENT TO:The Judges DESCRIPTION: LOCATION:SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE CHECK HERE IF ADDITIONAL COMMENTS ARE ATTACHED	SCHOOL NAME:		
SENT TO: The Judges DESCRIPTION: LOCATION: SPEC REF: SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE	RFI No.:	TIME SUBMITTED:	
DESCRIPTION: LOCATION: SPEC REF: SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE	PROJECT:	UCI East Campus Student Apartments	
DESCRIPTION: LOCATION: SPEC REF: SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE	SENT TO:	The Judges	
SPEC REF: SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE	DESCRIPTION:		
SPEC REF: SHEET NO: OTHER: INFORMATION REQUESTED: SIGNATURE DATE			
OTHER: INFORMATION REQUESTED: SIGNATURE DATE	LOCATION:		
OTHER: INFORMATION REQUESTED: SIGNATURE DATE	SPEC REF:	SHEET NO:	
SIGNATURE	OTHER:		
SIGNATURE			
	INFORMATION RE	QUESTED:	
	SIGNATURE	DATE	
			_

SCORE SHEET

UCI EAST CAMPUS STUDENT APARTMENTS Irvine, California

I. PROPOSAL PORTION

2A PHASING AND SCHEDULING

Logical phasing scheme that satisfies Owner's requirements Logical layout and sequence

Accuracy of answers to questions

16%

2B STAGING AND LOGISTICS

Correct location of required components

11%

3 ESTIMATING

Bid Breakdown

Accuracy of Direct and Indirect Costs

Completeness/accuracy of subcontractor bid analysis

Owner Upgrades & Kitchen Reconfiguration

Accuracy of quantity takes-offs

Completeness of components for each system

Correct pricing for upgrades

26%

4 PLAN READING & PROJECT ENGINEERING

Accuracy of responses

21%

WRITING SKILLS

Proper format

Grammar, punctuation, spelling

Organization and clarity

Logical, persuasive

7%

II. PREQUALIFICATION BROCHURE & ORAL INTERVIEW

A. PREQUALIFICATION BROCHURE

Required elements present

Applicability to Project

Neatness, professional appearance

B. ORAL INTERVIEW

Demonstration cf knowledge of Project (presentation not "canned")

Focus on key project issues

Response to judges' questions about written portion of problem

Response to judges' questions about presentation

Ability to handle "zingers" -- "thinking on your feet"

Presentation Skills

Participation by all team members

19%

PENALTY

Penalty for late Proposal

Deduct 10%

Section 2A Phasing and Scheduling

UCI East Campus Student Apartments Irvine, California

Premise

The entire project was originally scheduled to complete before the fall quarter of 2008. However, due to the late start of the project, this is no longer feasible. The Owner still needs some buildings released before the fall 2008 quarter, with the remainder to open in phases coinciding with school year quarters. The criteria are as follows:

Phase I (Fall Quarter—October 1, 2008)
Release 16 undergraduate buildings
Complete the Maintenance Building (or build temporary structure)

Phase II (Winter Quarter—January 1, 2009)
Release eight (8) undergraduate buildings

Phase III (Spring Quarter—April 1, 2009)
Release eight (8) undergraduate buildings

With the release of each phase, residents must have access to adequate parking spaces and laundry/commons facilities. In addition, the ten (10) graduate buildings may be released as a part of any phase, but should be released all at once. Construction will commence October 1, 2006.

<u>Assignment</u>

1. Detailed Schedule

As a preconstruction exercise, the Owner has requested a detailed schedule of the Recreation Building. Prepare a detailed bar chart schedule of the building from the start of rough framing. Use only the activities listed in Exhibit 2A-1. The schedule must clearly indicate the early start and early finish dates for all activities, activity durations and all logic ties between activities. Separate the schedule into two categories—interior and exterior. Clearly identify the critical path activities. Assume a five-day work week with no holidays and a hypothetical *January 1, 2005* start date.

2. Summary Schedule

Your company must establish a phasing scheme that is most effective and practical in terms of logistics, access, and construction efficiency, as well as with regard to optimizing resident living. Create a bar chart summary schedule to illustrate your phasing scheme. Organize the activities into Phases I, II, and III. List each building as one activity using the durations shown below.

Residence Building Type A	200 days
Residence Building Type B	240 days
Residence Building Type C	210 days
Residence Building Type D	220 days

In addition, include the following activities in the summary schedule where appropriate.

Graduate Building parking area Palo Verde & Arroyo Road Paving Undergraduate Building parking area 1 Undergraduate Building parking area 2 Undergraduate Building parking area 3 Underground Utility Mains Riparian area protection Commons/Laundry Building Maintenance Building	15 days 15 days 15 days 15 days 15 days 45 days 40 days 150 days each
Recreation Building	300 days
-	

Criteria to consider:

- Allow at least two (2) weeks at the end of each phase for final Owner punch-out and correction. Indicate this activity, as well as finish milestones.
- The concrete contractor will work one crew that can produce building slabs at the following rates:
 - Bldg. A 5 days
 - o Bldg. B 8 days
 - o Bldg. C 6 days
 - o Bldg. D 7 days
 - Recreation Building 8 days
 - All other buildings 5 days
- The paving contractor can mobilize two separate crews, if required to complete all the paving on the project.
- The Riparian area must be protected during all phases of construction from both vehicular and foot traffic. This work should be completed before the commencement of rainy season around mid to late November.
- Observe the following holidays: New Year's Day, MLK Jr. Day, President's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day and day after, and Christmas Day.

	er the following questions regarding hypothetic situations. Do not incorporate sues on your schedules.
1.	The Owner experienced water damage and mold issues in past projects and has requested that your firm test the entire building exterior for water infiltration. Explain how you propose to do this, when it should occur in the construction sequence and how it would impact the critical path of the Recreation Building.
	The cabinets and casework for the Recreation Building, which were ordered from overseas, have been delayed in route for one month. The manufacture informed you of this one week before they were to arrive on site for installation. Explain how this will impact your schedule and what you can do to minimize the impacts.
ite	
_	ems to be turned in
De	etailed schedule of Recreation Building
De Si	

Page 3 of 4

Exhibit 2A-1

Detailed Schedule Activities

Appliances	10	days
Cabinets and casework	25	days
Doors and frames .	18	days
Drywall, prelim and production	58	days
Exterior paper/metal lath/trim	14	days
Exterior scaffold - erect	9	
Exterior scaffold - remove	17	days
Fabricate and install stairs	17	days
Fabricate elevator	48	days
Flooring and tile work	44	
Install elevator	20	days
Install roofing	13	
Install windows 1st floor	28	days
Install windows 2nd floor	14	days
Insulation	5	days
Interior paint and wall coverings	40	days
Interior paint prime	10	days
Lobby waterwall construction	35	days
MEP finishes	35	days
MEP rough-in	81	days
Mini-theater & Mtg room casework		days
Plaster brown coat	3	days
Plaster finish coat	27_	_days
Plaster scratch coat		days
Rough framing	38	days
Stamped concrete @ Arcade		days
Stock roof		days
Wood ceilings and trim	29	days

Section 2B Staging and Logistics

UCI East Campus Student Apartments Irvine, California

Staging Plan

Prepare a Staging Plan for each phase of work to be submitted to the University, Architect and Building Department for approval. The Staging Plan should outline the contractor's perceived site logistics and be consistent with the Phasing Plan developed in Section 2A. As well, the "Construction Issues" listed in this section must be incorporated into the preparation of the Staging Plan.

The Staging Plans may include, but not be limited to, the following items:

- Fire road construction as required by local Fire Department
- Protection of Riparian Area
- Temporary fencing
- Temporary construction gates
- Temporary traffic barricades
- Pedestrian protection
- Project team offices
- Parking areas for construction personnel
- Subcontractor storage and staging areas
- Long-term storage
- Path of travel for mobile crane

Items to be turned in

Three separate Staging Plans (one for each Phase) Detailed section of canopy

Staging and Logistics – Construction Issues

UCI East Campus Student Apartments Irvine, California

- 1. The project is being built in open space on university property. The site is bound by Culver Drive to the east and open space to the south, west and north. Existing single family homes are across the street and Culver Drive acts as a thoroughfare in and out of that development.
- 2. Arroyo Drive and Palo Verde Road are private streets which are to be constructed as a part of this project. The site will be accessible to vehicle traffic from the north only and the Arroyo Drive improvements are to be temporarily barricaded south of the project site. The site is not to be accessible from Culver Drive until such time as all phases of work are complete.
- 3. The site must be secured after the construction of Palo Verde Road until such time as all three phases of work have been completed.
- 4. The Riparian Area must be protected prior to commencement of any of the phases of construction. Protection shall remain in place until all phases of work have been completed.
- 5. Prior to the commencement of building construction a temporary fire road must be constructed and is to be maintained throughout the project duration. At a minimum the road is to be constructed of a compacted gravel base no less than 6" thick and compacted to 90% relative compaction.
- 6. Fire Department requires that hydrant facilities be available at all construction areas prior to commencement of wood framing. No temporary fire facilities are allowed.
- 7. All underground utilities must be installed and in place prior to concrete foundations. That includes rough-in of all utilities; sewer, water, fire water, storm drain and electricity. No saw-cutting or coring will be allowed. Note that gas can be "stubbed" to the building at a later date.
- 8. Based on historical data and long-range weather forecasts there is a prediction for substantial rainfall in the coming year. The university has requested that storm drain improvements in Arroyo Drive and Palo Verde Road be installed as early as possible for use during winter months to avoid potential delays and assist in site remediation on a continual basis.

- Forty-foot (40') trailers will be used on site (within the property lines of the project) to house your project team. Site offices will be accessible at all times for use by construction personnel, deliveries, mail delivery and project meetings.
- 10. Upon completion of each phase, it will be necessary to provide security between student housing and construction areas. The university has requested that construction fencing be in place to clearly isolate the student population from on-going construction activities.
- 11. Due to the close proximity of the housing and parking lot facilities the university has requested protection of pedestrian walkways adjacent to on-going construction. Canopies shall be at least 8' tall with a ceiling and shall be lighted at all times. In addition to locating of canopies, the Building Department has requested that you provide a detailed section of canopy construction.
- 12. It will be necessary to provide a separate gated construction entrance off of Arroyo Drive for future phases of work. This entrance will be for use by construction and university maintenance personnel and will be off-limits to students and/or public access.
- 13. Construction personnel are to park on site during construction of all phases of work. However, upon completion of each respective phase the associated parking areas will be turned over to the University for student use. Based on the subcontractor parking requirements there is a need for at least 150 parking stalls at all times.
- 14. Staging and stockpiling of material and equipment is to be done within the limits of the property line. No offsite storage or staging is allowed. Based on the amount of manpower and material required it is anticipated that this area be no less than 27,500 square feet per phase.
- 15. Trusses for the entire project have been purchased and will be delivered in one (1) single delivery. Due to the size of this shipment it will be necessary to store material onsite for use during respective stages of work. The truss manufacturer has advised the project team that a contiguous area no less than 50,000 square feet will be required to store and stage trusses.
- 16. A mobile crane will be used for framing and roof construction. The crane will require access to all buildings and will be used during all phases of work. According to the specifications, there is a requirement for a 24' turning radius and a 15' wide clear path of travel.

Section 4 Plan Reading and Project Engineering

UCI East Campus Student Apartments Irvine, California

How to Complete this Section

Read the questions carefully and write the answers in the space provided. All of the answers can be obtained by using the construction documents, the cut sheets, product data and information provided in this section. All dimensions and quantities should be calculated without the use of any waste or overage factors. Be sure to show ALL your work; partial credit will be considered even if the final answer is incorrect. Use attached sheets 2-8 for your answers.

Exhibits Included in this Section

Exhibit 4-1 (2 pages)

Exhibit 4-2.1 (1 page)

Exhibit 4-2.2 (1 page)

Exhibit 4-2.3 (1 page)

Exhibit 4-3.1 (1 page)

Extribit 4-0.1 (1 page)

Exhibit 4-3.2 (1 page)

Exhibit 4-3.3 (1 page)

Exhibit 4-3.4 (1 page)

Exhibit 4-4 (3 pages)

Exhibit 4-5 (1 page)

Exhibit 4-6.1 (1 page)

Exhibit 4-6.2 (1 page)

Exhibit 4-7 (4 pages)

Exhibit 4-8.1 (3 pages)

Exhibit 4-8.2 (1 page)

Items to be turned in

Completed sheets 1 - 8

Response to question #9

Response to question # 20

Sch	ool N	ame
1.	(Eas	ng the City review of this project, local citizens living adjacent to the project of Culver Dr.) expressed their concern about possible noise levels from the lent balconies. To accommodate this concern, the Architect added storefront had barriers at various patios and balconies.
	In a	ccordance with the plans, provide the following:
	a.	Building numbers, type and style where Sound Walls occur:
	b.	Total Square Feet of Storefront (use reverse side if more space is needed):

	C .	Referring to sheet D-7, what trades other than storefront would be affected to coordinate the installation?
2.		accordance with the Structural Plans and Exhibits 4-1 provide the following rmation:
	a.	Slab on Grade thickness:
	b.	Total Number of Shear Walls in a typical Building Type A:
	C.	List the shear wall types that occur on the first floor of Bldg Type A:
	d.	Assuming an ATS Hold-down system, provide the rod diameter for a No. 33 Hold-down:
	e.	What is the plywood thickness of a No. 12 shear wall?
3.		at is the overall door jamb thickness (throat size) of a typical bedroom door
	a.	Provide a detail (section cut) of this scenario.

Ar	e any windows required to have an STC rating? If so, please specify location:
.—	hat is the typical window and door header height as indicated on the drawings?
ln	reference to the trim on the exterior elevations, provide the following:
a.	What is the trim material:
b.	What is the typical size of the trim around the jamb & head of a window?
C.	Explain the installation sequence of the trim and provide the detail reference(s):
	ovide the following information regarding the Community Center (Recreation) uilding:
a.	What occupancy type is indicated?
b.	What is the construction classification?
C.	What is the total square footage of the Fitness Room?
d.	What size is the mirror on the fitness room wall?
Α	ssume the Architectural drawings govern where the drop ceilings (soffits) occur.
а	Does unit type 4 architectural floor plan (Exhibit 4-2.1) provide sufficient soffits for the mechanical equipment in accordance with Exhibit 4-2.2? If not, mark up and attach Exhibit 4-2.3 indicating additional soffit locations necessary to accommodate all mechanical equipment.

- b. Mechanical drawings call for some of the duct to run in the joist bays per detail G on Exhibit 4-3.1. Does the direction of the duct run per the Mechanical unit type 3 (Exhibit 4-3.2) coincide with the direction of the joists per the Structural Drawings (Exhibit 4-3.3)? If not, more soffits will be required at these locations. If necessary, mark up and attach Exhibit 4-3.4 indicating any additional soffit locations.
- 9. The Owner is being pressured to remove the unsightly mildew on the studs and joists. The University and Owner are not only concerned with the potential health hazards of this mildew, but of its possible effect on the integrity of the building structures themselves. However, because of the good relationship your company has established with the Owner, all are confident the removal work you and your subcontractor are performing will cause these fears will to subside.

The framing is only 25% complete and already the framing subcontractor has requested reimbursement of \$75,000 for actual costs spent removing the mildew. In addition, both time and material are being expended by your company to assist the framing subcontractor with the removal process. These costs are not included in the \$75,000. Furthermore, as this work was not anticipated, no budget for the work was included in the G-Max Contract with the Owner or in the framing subcontract.

Your company has used this framing subcontractor on many jobs and has a great relationship with them. On every occasion, including this current project, they have come through on very tight schedules. This track record has helped to ease your company's concerns regarding the \$100,000 per day liquidated damage clause in your contract with the Owner. When you signed the framing subcontractor up, the lumber prices where very high. Since the framing has commenced, the market has softened significantly; the subcontractor, therefore, is realizing a large savings on the lumber. The Owner is not aware of these savings. Considering both your relationship with the Owner and subcontractor, how do you resolve this situation? Do you ask the Owner for a change order to recover the costs for both the framing subcontractor and your company? Does your company absorb all the costs? Do you ask the subcontractor to absorb some cost?

Prepare a letter to your Project Manager to explain how you are going to approach and deal with this situation.


10.	What Detail would you use for a One Hour Party Wall Condition?
	a. Are Sound Attenuation Blankets required?
11.	Your Cabinet & Countertop subcontractor wants to verify a few items prior to fabricating. Provide the following:
	a. Height of a typical island countertop:

	b.	Height of the island countertops at the ground floor:
	C.	Location and quantity of removable base cabinets at the kitchen sink:
	•	
	d.	Provide a list of units (addresses) where the kitchen sink base cabinet will be removed:
12.	Wh	at doors are required to have an undercut?
	a.	What size is the undercut?
13.	•	ecify the two locations where you would find the typical eave overhang ension:
	a.	Do the two locations specify the same dimension?
	b.	Provide the dimension(s):
14.	Pro	vide the pitch of the roof and the typical roofing material:
15.	Usi	ng Exhibit 4-4 provide the following information:
	a.	What circuit are the outlets in Bedroom No. 1 assigned to?
	b.	What is the maximum wattage for the living room light fixture?
	C.	How many smoke detectors are in this unit?
	d.	At what height are you to mount the receptacle near the sink of Bath 2?

16.	Usir	ng Exhibit 4-5 provide the following information:
	a.	How many area drains (sump boxes) are shown around Building 615?
	b.	Is point A indicated on Exhibit 4-5 at a higher or lower elevation than Building 615 finish floor?
	C.	Approximately how many feet of 8 inch PVC drain pipe is shown on the Exhibit?
17.	Usir	ng Exhibit 4-6.1 provide the following information:
	a.	What size is the main Building drain line?
	b.	How many Building drain lines are there?
	C.	What waste vent number is designated for the lavatories of Bath No.1?
	d.	How many total fixtures are provided in a Undergraduate Unit Type 3?
	e.	A Water Closet has considered a three (3) drain unit fixture. Using Exhibit 4-6.2 what is the total Fixture Unit count for the Waste Vent Riser No. 16?
	f.	Also using Exhibit 4-6.2 what is the vent pipe size of Waste Vent Riser No. 16?
18.		accordance with Specification Section 09250 (Exhibit 4-7) answer the following estion:
	a.	What type of Gypsum Wallboard is required at the walls of the bathrooms?
	b.	At what location(s) are "bullnose" corner beads required?
	C.	What type of Texture Finish is required?

- 19. The Owner has requested various Telecommunication outlets be installed in the project. Using the appropriate symbols and the furniture layout (from Exhibits 4-8.1) mark the locations of the following information on Exhibit 4-8.2:
 - a. Every bedroom shall have one (1) Video outlet, and one (1) Voice/Data outlet, both mounted 18" AFF.
 - b. Every living room shall receive one (1) combination Data/Video outlet mounted 18" AFF.
 - c. One (1) Voice outlet shall be mounted above the island countertop at 52" AFF.
- 20. The Owner has hired a consultant to review waterproofing issues, both as shown on the plans and the actual jobsite installations. In the Consultant's opinion the window installations are sub-par. His biggest concern is the sequence of installation of the self-adhering waterproofing membrane at the window jambs. Although the Consultant's installation sequence is different from the Contract Documents, the Owner would like you to adhere to it. To do this would require the removal and reinstallation of approximately 100 windows at various Buildings, some of which have been plastered. To remove and reinstall the windows, your subcontractor is asking for \$500 per window. Potential costs to replace windows damaged during the removal, or costs related to the plaster, are not included. The Owner has made it clear to you that he does not want to pay for this re-work. To make matters worse, your company's history has shown the existing installation sequence (which is shown on the Architect's drawings) has resulted in minimal leaks compared to the installation sequence being requested by the Consultant.

Please prepare a draft letter to your Owner stating your company's stance on this issue.




_	SHEAR M	ALL SCHEDULE	
5YM.	MATERIAL	PANEL NAILING	5ፆአ ወ
\odot	% KSP.	8d € 6° ∞ EN	16d e
	P11. 24/0 ©	8d € 12° ∞ FN	6' oc
()	% NSP.	86 0 4" oc EN.	16d 9
	P.U.= 24/0 @	8d 0 12" oc FN.	4" oc
Ø	% MSP.	8d 0 5' oc EN.	16d e
	P.I.I.= 24/0 @@	8d 0 12' oc FN.	3' oc
\Diamond	% MSP.	8d 0 2' 00 EN	16d €
	PJ.L: 24/0 @®	8d 0 12' 00 FN	2" oc
(3)	1/2" STRUCT, I M.S.P. P.I.L. 52/6 (2)(3)	lod @ 2' oc EN.	16d € 2° oc

- S.F.N. a SOLE PLATE NAILING, USE BOX NAILS OF BETTER AT SPACING SHOWN UNLESS SPECIFIED OTHERWISE ON PLAN.
 ALL EDGES SHALL BE BLOCKED.
- 5" NORMAL FRANING SHALL BE USED AT FOADATION SILL FLATES AND ALL FRANING INDICERS RECEIVING EDGE NALING FROM ADJITING SHEAR FANELS. PLYMOOD JOINT AND SILL FLATE NAILING SHALL BE STAGGRED ON SIX MONERORS

NOTES:

- WISP, INDICATES WOOD STRUCTURAL PANEL WOOD STRUCTURAL PANELS SHALL CONFORM TO UBC STANDARD 23-2 or 23-3. aì
- NAILS FOR MOOD STRUCTURAL PANELS TO BE COMMON OF GALY, BOX. SALVANZED NAILS SHALL BE HOT-DIFFED OR TIMBLED.
- NAILING APPLIES AT ALL STUDS, PLATES AND BLOCKING
- PROVIDE BOSE HAILING TO POSTS AT HOLDDOWN LOCATIONS. dΙ
- USE 2x STUDS @ 16" ox AT ALL SHEAR MALLS, UND.
- SEE FOUNDATION PLANS FOR ANCHOR BOLT SIZE AND SPACING

SHEAR WALL SCHEDULE



- TES.
 RIN LONG DIMENSION OF PLYMOOD ACROSS
 (PERPENDICULAR LO) JOISTS AND RAFTERS.
 STASSER BOD JOINTS 2"-O" IMPNIMM.
 BOUNDARY NALING APPLIES TO PERDICITER
 PLATE LIMES, CHORDS, TIES, AND AS CALLED

- PLATE LIPES, CHORDS, TIES, AND AS CALLED FOR OH DRAWNESS.
 SEE PLANS FOR NAILING.
 NAILS SHALL HAVE HIM 18" EDGE DISTANCE.
 ALL JOISTS AND RAFTERS SHALL BE LAID OUT IN A 4"-O" MODILE TO COINCIDE WITH PLYMODD. LISE TONISE-AND-GROVE PLYMODD AT PLOODS.
 NA ESS NOTED OTHERWISE.
 SEE DETAIL BY FOR FRAMING HASTER PLYMODD JOINTS AND OFFICER FRAMING THE PLYMODD JOINTS AND OFFICER DIE TO RAFTER OR JOIST LAP SPLICES.





PLYWOOD DIAPHRAGM DETAIL

					00078				
PLATE	EA. SIDE of		TYPIS	MPICAL PLATE SPLICE IND 9 16'00 EITH SPLICE TYP. of PLATE					
(2) 16d PLATE	EA SIDE of SPLICE				MILLION MCH SPLIKE				
SIDE of			AT	512	SMESON PUNO.				
	SIDE of THE WALL?	(4) ISG EA SIDE of PLAIE SPLICE TYP ALT: SIMPSON STIZE (2) ISG EA SIDE of PLAIE SPLICE SIDE of STIZE SON STIZE	SIDE of STEEL	(4) Idd EA SIDE of PLATE SPLICE TYP ALT: SIMPSON STIZZ (2) Idd EA SIDE of PLATE SPLICE III SIDE of PLATE SPLICE III SON STIZZ	SIDE of SITE2				

No. Date Description 11.07.02 OWNER REVIEW 11.26.02 C.D. SET 104454 J. 0 2002

Consultante

1



DALE CHRISTIAN/ STRUCTURAL ENGINEER, INC. CONSULTING & DESIGN 1748 West Katella Avenue Suite 208 Orange, CA. 92867 714 997 1145 714 997 3857 FAX DALE A. CHRISTIAN SE 2705


Project:


UCI · EAST CAMPUS STUDENT APTS. PHASE 1 **IRVINE** CALIFORNIA

RECEIVED


JAN 1 6 2003


BENCHMARK







N








PLAN 3 FIRST FLOOR






KILOWATT KILO-VOLT AMP


LIGHTING

TRANSF TRANSFORMER


TWIST-LOCK CONSTRUCTION



UNIT "P2"



NOTE: PROVIDE FOR SUDSING ON ALL THREE STORY KITCHEN SINKS, TUBS, & WASH, MACHINES WASTE & VENT RISER DIAGRAMS



SECTION 09250

GYPSUM WALLBOARD

PART 1 - GENERAL

- DESCRIPTION: Division 1 applies to this Section. Provide gypsum wallboard complete 1.01 as indicated, specified, and required.
 - Work In This Section: Principal items include:
 - Gypsum wallboard finish on walls and ceilings. 1.
 - Interior tile backer board. 2.
 - Joint, edge, corner, and fastener finishing. 3.
 - Sound insulation in gypsum wallboard partitions. 4.
 - Sound and airsealing Work of this Section. 5.
 - RECEIVED Skimcoat finish where scheduled. 6.
 - Elevator shaft wall system. 7.

JAN 1 6 2003

Related Work Not In This Section: B.

BENCHMARK

- Wood stud support framing. 1.
- Thermal insulation. 2.
- Painting. 3.
- SUBMITTALS: Refer to Section 01300 for procedures. 1.02
 - Product Data: Submit covering wallboard installations, including accessories, A. finishing, sealing, and manufacturer's written installation instructions with copies of Code approvals for each wall, ceiling, and shear wall system.
 - Samples: Submit such Samples as Owner and/or Architect may request. В.
- JOB CONDITIONS: Make a detailed inspection of areas and surfaces to be enclosed or covered by gypsum drywall and arrange for correction of defective workmanship or 1.03 materials. Ascertain that other Work enclosed by drywall has been inspected and approved before starting installation; otherwise, uncover as directed at no extra cost to Owner.

PART 2 - PRODUCTS

MATERIALS: 2.01

Gypsum Wailboard: ASTM C36, provide 5/8" Type X gypsum board, tapered edges for exposed surfaces, regular grade by the Code. For walls in toilets and A. bathrooms, and where indicated, provide Type W/R or Type X W/R water resistant boards as required by the jurisdiction and where recommended by the Gypsum Association.

JAN 1 6 2003

Gypsum Wallboard 09250 - 3


UCI – East Campus – Phase 1 Student Apartments Irvine, California

BENCHMARK


- D. Openings: Accurately cut and fit the wallboard at openings. At door and other openings, cut wallboard to continue across area above opening head; do not cut board to both jambs and fill in area over openings with separate pieces. Make the dimension from joint over head of an opening to jamb of openings 6" minimum. Stagger joints on opposite side of partition. Maximum opening around electrical outlets 1/8" calked.
- E. Single Layer Walls: Place wallboard horizontally with long dimension across the studs or in one-piece vertical heights, vertical joints centered on supports and staggered on walls so as not to occur on opposite sides of same stud. Secure to each stud and tack with screws keeping screws 3/8" from edges.
- F. Multi-Layer Walls: Apply first layer same as for single layer walls, all joints in subsequent layers staggered with respect to first layer.
- G. Ceilings: Apply wallboard with long dimension at right angles to the framing, end joints staggered and centered over framing. Use boards of maximum practical length to minimize end joints and properly support around cutouts and openings. Secure with screws or nails.
- JOINT TREATMENT AND FINISHING: Apply tape bedding compound, tape, and at least three coats of finishing cement on exposed joints, and other joints as required for sound insulating or fire-rated construction. Apply joint cement and two or more layers of finishing cement over screw or nail heads. Treat all inside corners with joint cement, tape, and finishing cement. Treat all outside corners with corner beads and finishing cement. Provide metal casing beads at all edges of gypsum wallboard which abut ceiling, wall, or column finish, and elsewhere as required, such as openings, offsets, etc. Make all exposed joints, trims, and attachments non-apparent following application of paint or other finishes; if the joints and fasteners are apparent, correct defects as directed with no extra cost to Owner. Seal the raw edges of plumbing openings and of boards that have been cut to fit with manufacturer's recommended sealant brushed on. When entire installation is completed and prior to installation of finish materials by other trades, correct and repair broken, dented, scratched, or otherwise damaged wallboard surfaces.
- 3.03 AIR SEALING: Seal connections between shaft walls, ducts, plenums, and building structure airtight with specified calking compound or tape and cement, including vertical shafts.
- SOUND INSULATED PARTITIONS: Install sound insulation continuously between studs from finish floor to top of wall in which it occurs. Where cutouts are made for J-boxes, conduit, piping, and like items, back wall insulation with insulation so that one additional layer of insulation at least 24" wide and high is placed in back of cutout. Snugly fit in place free of gaps or holes. Calk between the wallboard edges and floors, walls, and at structures above other than acoustical ceilings with calking compound, forming a complete perimeter seal. Calk around outlet boxes and other penetrations in same manner. Where resilient channels occur a separate fastener will attach the RC channel to the framing member. The gypsum wallboard will be attached to the RC channel and will at no time fasten directly to a framing member.


VOICE, DATA & VIDEO SYMBOLS

. ▼	VOICE CUILET, CABLE TYPE AS SPECIFIED, NOUNTED 418° A.F.F. LALESS MOTED OTHERNISE
▼.	VOICE OUTLET, CABLE TYPE AS SPECIFIED, LIQUINTED 418" AFF. UNLESS MOTED OTHERTISE, X-RUMBER OF CABLE TERRINATIONS PER LOCATION AS INDICATED
▼	VOICE DUTLET, CABLE TYPE AS SPECIFED, MOUNTED +52" A.F.F. UNLESS NOTED OTHERWISE
₩	voice cutlet, cable type as specified, mounted +6" above counter or splash unless hoted otherwise
*	PUBLIC TELEPHONE OUTLET, CABLE TIPE AS SPECIFED, WOUNTED HOIGHT AS SPECIFED
~ "	VOICE OUTLET, NO INSTRUMENT, CABLE TYPE AS SPECIFED, MOUNTED +18" AFF. UNLESS NOTED OTHERWISE
▼◆	VOICE OUTLET, KEYNOTE (1) APPLIES
₹ .	PONER/COMMUNICATIONS POLE THTH X-HUMBER OF VOICE TERMINATIONS PER LOCATION
	VOICE OUTLET, CABLE TYPE AS SPECIFIED, FLUSH FLOOR MOUNTED
	VOICE OUTLET, CABLE TYPE AS SPECIFED, SURFACE MOUNTED MONUMENT
\triangle	DATA GUTLET, CABLE TYPE AS SPECFED, MOUNTED +18" AFF. UNLESS NOTED OTHERWISE
Ą	DATA CUTLET, CABLE TYPE AS SPECFED, MOUNTED +18" A.F.F. UNLESS NOTED DIFFERENCE, X-MANGER OF CABLE TERMINATIONS FOR LOCATION
₹	DATA CURLET, CARLE TYPE AS SPECFED, MOUNTED +6" ABOVE COUNTER OR SPLASH UNLESS HOTED CITERRISE
\triangle_{\diamondsuit}	DATA OUTLET, KETHOTE (1) APPLES
Å	PONER/COLORUNICATIONS POLE WITH X-NUMBER OF DATA TERMINATIONS PER LUCATION
	DATA CUTLET, CHOLE TYPE AS SPECIFIED, FLUSH FLOOR MOUNTED
	DATA QUILET, CABLE TYPE AS SPECFED, SUIVACE NOUNTED NORMENT
▼	VOICE AND DATA OUTLET WITH 1 VOICE RUN AND 1 DATA RUN, CARLE TYPE AS SPECIFED, MOUNTED 418" A.F.F. LINLESS MOTED OTHERWISE
₹	VOICE AND DATA CUTLET WITH X-MLABER OF VOICE PERMANATIONS AND Y-MUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFED, MOUNTED +IN* A.F.F. LIRLESS MOTED OTHERWISE
√	YOKE AND DATA OUTLET WITH I VOICE RUN AND I DATA FUM, CABLE TYPE AS SPECIFIED, MOUNTED +18" A.F.F. LINLESS MOTED OTHERWISE.
₹	VOICE AND DATA OUTLET, CABLE TYPE AS SPECIFED, MOUNTED +6" ABOVE COUNTER OR SPLASH UNLESS NOTED OTHERWISE



` 	EXHIBIT 4-4														
· ·		Bulldings Finish 180.	Community contor	Community Center Pool Finish 190.	Scharachty Camer Study Rooms		Offerer banks for each room sholf have multi-ganged face plates		Ramartas	Withen	Living Room	Bedroom	Bathroom	Work-in Closet	
	_	>							lbr. R						
·		8	120	120	\$21				Voite	120	120	120	120	120	
·	,>	51	97	51	ž				# E	5	33	25	æ	2	
		Philips PL-S 13/627	Philips Pt9 13/627	Philips PL-5 13/627	Rolles F32787830				Lomp Type	Philos 7377/730	Philos PtC 1.38/827/4P/atto	Philos PL-C 1.34/827/4P/aHs	Philips PL-C 158/827/4P/aito	612/46/128/MC1 212 14.698	
-	-	-	~		\$ E		> <		Š 8	2	2	2	2	-	
1		SL-8160-PL13~(Inlen)	51-8113-PL13- bottory pock	S8105-PL13-	AW-SP-744-2-C- (volta)-5J-WA-08		IduiliSel/Hutilset Pro Series		Catalog /	Phoebing Claud 15213-	Thousand Oaks IDSZ13E-3H-120Y- W/LPS	Thousand Octs IDS21.3E-3H-120V- W/APS	FEZ13-E-84-120V-	Eagle 134 E WH	
1	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Ughtech or Cpproved equal by: Bego AAL	Ughlach of approved equal by: 8ega AAL	Lightech or reproved equal by: Bega	Corulto or opprovage equal by Staglite Prudentical		Lightofer or approved equal by: Lukran Lukran		Manufacturer	Energreen of opproved equal	Teron or opproved equal	Teran or approved educi	Teron of approved aqual	Teron or approved equal	
Not used	200	Recessed compact fluoriscant steplight eith Inlayed balast	Recessed compact fluorescent studight with Integral balliary and energency balliary pack	Recreed compact Pubmecant simplifit with integral balloat	Indirect/Unecol -Endor two-kump Two capeans	Dimming controls for Clubhouse	Provide four-scene preset soll bus dimining epidems for reams with dimming		Description	Surfecs-mounted theor fluorescent with errep-erround lens, integral electronic beliest	Surface-mounted compact fluorescent decorative timiseins with treated diffuser, brushed nichel finish and se electronic balkat	Surface-mounted compact fluoreacent decertifier further failed officer, brished richel finish ond an electronic before	Surface-mounted compact fluorescent luminoire with frasked offices, brushed nickel finish and an alectronic bolicat	Surfoce-mounted compoct fluorescent huminoing with frosted diffuser, white finish and on electronic bollest	
_	20	1.288	2 448	s Liu	\$				Ē	*	6	υ	٥	5	
	-		1												





UCI - East Campus - Phase 1 Student Apartments Irvine, California

3.5 SKIM COAT FINISH: Provide where scheduled, apply USG Product that will produce a "smooth" or "knock down" texture finish as approved by Owner and/or Architect. Apply after taping and screw head finishing is dry and sanded to produce surfaces free of trowel marks or other defects.

END OF SECTION

RECEIVED

JAN 16 2003

BENCHMARK

RECEIVED

UCI – East Campus – Phase 1 Student Apartments Irvine, California

JAN 1 6 2003

Gypsum Wallboard 09250 - 2

BENCHMARK

- B. Interior Tile Backer Board: For walls in toilets and where indicated on drawings or required, provide Durock or WonderBoard Tile Backer Board. Install per manufacturer's recommendations.
- C. Screws: ASTM C646, corrosion-resistant self-tapping bugle-head spiral threaded type, minimum 1" long except 1-5/8" for double layer walls or longer where RC channels are used, lengths to penetrate all supporting metal at least 3/8". Furnish specially hardened type screws where required by code for support.
- D. Drywall Nails: ASTM C514, supplied or recommended by the wallboard manufacturer, No. 13 gage 1-5/8" long, 19/64" head, Dry Tite, acid etched or No. 098 gage, 1-3/8' long annular ringed 6d, cooler nails.
- E. Metal Trim and Corner Beads: Of electrogalvanized steel with taping flanges, as manufactured or recommended by drywall manufacturer, corner beads at all outside corners and "J" shaped trim members where abutting other materials. Provide "bullnose" corner beads at public areas.
- F. Finishing Materials: ASTM C475, joint tape, joint bedding compound, finishing cement, adhesive, and laminating compounds supplied or recommended by wallboard manufacturer.
- G. Calking Compound: Permanently non-hardening type as supplied or recommended by wallboard manufacturer.
- H. Sound Insulation: Friction fit fibrous glass batts of minimum 3-1/2" thickness unless otherwise indicated, nominal 2.80 pcf density by USG.
- I. Resilient (RC) Furring: ASTM C645, minimum 25 gage, hat shaped, designed for sound reduction by gypsum wallboard manufacturer.

PART 3 - EXECUTION

- 3.01 INSTALLATION OF GYPSUM WALLBOARD:
 - A. General: Perform wallboard installation and finishing according to ANSI A997.1 and the wallboard manufacturer's instructions. Do not install wallboard until building is weathertight. Conform to fire-rating requirements, Building Code approvals, and requirements herein.
 - B. Temperature: Maintain minimum 65 degrees F within building during installation. Furnish ventilation to eliminate excessive moisture.
 - C. Fasteners: Install screws or nails so heads are below wallboard surface without breaking surface paper around the fastener. Space screws according to listed assembly requirements.

