

Exhibit A

SCHEDULING CONSIDERATIONS

1. The deck concrete mix has reached 70% strength in 48 hour tests.
2. The MEP subcontractor requires 3 days to install all conduit, block-outs, and hanger mounts in the decks. There are minimal vertical concrete elements with MEP installations and these should be disregarded for the sake of this exercise.
3. The reinforcing subcontractor has informed you that installation of deck reinforcing steel and post-tensioning cable will require 3 days, not including inspection or corrections.
4. Sundt's place & finish superintendent has informed you that his crew can place and finish the full deck in one shift or two shifts as needed.
5. The Structural Engineer of Record will require 1 floor of 100% reshoring and 1 floor of 50% reshoring to adequately distribute the live and dead loads of ongoing construction activity.