

Exhibit H - Labor Rates & Productions

All values shown on this sheet have been developed for the sole use of this competition and are not intended to be reflective of actual market rates and/or vendor specific costs/productions.

LABOR RATES	\$ Value	Unit of Measure
CRAFT LABOR:		
AGGREGATE CREW HOURLY RATE	\$ 46.20	MH
ADMIN SUPERVISION* :		
OPERATIONS MANAGER	\$ 178.44	MH
AREA MANAGER	\$ 155.07	MH
PROJECT MANAGER - SR.	\$ 135.13	MH
PROJECT MANAGER	\$ 110.24	MH
PRE-CONSTRUCTION MANAGER	\$ 178.44	MH
PRE-CONSTRUCTION PROJ. MANAGER	\$ 144.27	MH
SENIOR ESTIMATOR	\$ 121.03	MH
ESTIMATOR	\$ 81.92	MH
GENERAL SUPERINTENDENT	\$ 143.51	MH
PROJECT SUPERINTENDENT	\$ 116.84	MH
FIELD SUPERINTENDENT	\$ 94.87	MH
PROJECT ENGINEER - SR.	\$ 91.06	MH
PROJECT ENGINEER	\$ 81.15	MH
LAYOUT ENGINEER	\$ 76.84	MH
CQC MANAGER/MEP Coordinator	\$ 93.60	MH
CQC ASSISTANT (Field Eng)	\$ 70.36	MH
SAFETY SPECIALIST	\$ 92.71	MH
ADMINISTRATION MANAGER	\$ 83.57	MH
PROJECT ADMINSTRATOR	\$ 63.88	MH
CLERICAL PERSONNEL	\$ 46.23	MH
CONTRACT ADMIN./PURCHASING	\$ 58.80	MH
DIRECTOR OF VIRTUAL CONSTRUCTION	\$ 115.19	MH
VIRTUAL CONSTRUCTION ENG	\$ 85.34	MH
VDC TECHNICIAN	\$ 65.41	MH
SUBCONTRACTOR QUOTES:		
FOUNDATIONS	<i>see quotes</i>	
FORMWORK SYSTEMS	<i>see quotes</i>	
REINFORCING PT/REBAR	<i>see quotes</i>	
READY-MIX CONCRETE	<i>see quotes</i>	
CONCRETE PUMPING	<i>see quotes</i>	
HOISTING / CRANES	<i>see quotes</i>	
LUMBER PRODUCTS	<i>see quotes</i>	

* Administrative Staff as required for project.

Exhibit H - Labor Rates & Productions

All values shown on this sheet have been developed for the sole use of this competition and are not intended to be reflective of actual market rates and/or vendor specific costs/productions.

"Production Quantity"

PRODUCTION RATES	\$ Value	Unit of Measure
SELF-PERFORM FLATWORK:		
STEEL TROWEL PLACE/FINISH SLABS	125.00	SF/MH
FLOAT PLACE/FINISH SLABS	145.00	SF/MH
BROOM PLACE/FINISH SLABS	150.00	SF/MH
ATLAS FORMWORK		
COLUMNS (ATLAS - 1st Level)	0.12	EA/MH
COLUMNS (ATLAS - Typical Level)	0.15	EA/MH
WALLS (ATLAS)	14.00	SF/MH
HIGH BAY HANDSET (ATLAS FORMWORK)	9.50	SF/MH
TYPICAL DECKS (ATLAS TRUSS TABLE SYSTEM)	17.00	SF/MH
PERI FORMWORK		
WALLS (PERI Trio)	13.75	SF/MH
WALLS (PERI Maximo)	16.80	SF/MH
COLUMNS (PERI Quattro - 1st Level)	0.16	EA/MH
COLUMNS (PERI Quattro - Typical)	0.19	EA/MH
DECK - PERI Gridflex hand-set (High Bay)	9.00	SF/MH
DECK - PERI Gridflex hand-set (Typical)	12.25	SF/MH
DECK - PERI Sky Table System (High Bay)	8.75	SF/MH
DECK - PERI Sky Table System (Typical)	22.00	SF/MH