

SAN DIEGO
 PH: 760-598-7855
 FAX: 760-598-5850



LA, ORANGE
 INLAND EMPIRE
 PH: 951-736-5470

Sundt Construction, Inc

DATE: 6/12/2015 Phone: 480-293-3196
 CONTRACTOR: Sundt Construction, Inc Fax: 480-293-3530
 ATTENTION: Cole Ficklin cficklin@sundt.com
 ADDRESS: _____
 PROJECT: California Baptist University

We are pleased to quote the following prices to provide concrete pumping services, in support of the above referenced project. Prices quoted will remain in effect through Duration of Project

BOOM PUMPS

Boom Length	Pump/Hr.	CY/Price	Min.Pump Chg	Vertical Reach	Horizontal Reach
28 Meter	\$55.00	\$2.00	4 HR	92'	79'
31 Z Meter	\$80.00	\$2.25	5 HR	103'	89'
32 Meter	\$60.00	\$2.00	4 HR	106'	93'
34 Meter	\$65.00	\$2.00	5 HR	112'	99'
36 Meter	\$70.00	\$2.00	5 HR	118'	105'
37 Meter	\$75.00	\$2.00	5 HR	121'	108'
38 Meter	\$80.00	\$2.00	5 HR	124'	111'
39 Meter	\$85.00	\$2.25	5 HR	127'	114'
42 Meter	\$90.00	\$2.25	5 HR	138'	124'
43 Meter	\$95.00	\$2.25	5 HR	138'	124'
47 Meter	\$110.00	\$2.50	5 HR	155'	142'
48 Meter	\$115.00	\$2.50	5 HR	158'	144'
52 Meter	\$125.00	\$2.50	5 HR	158'	144'
55 Meter	\$140.00	\$2.75	5 HR	167'	152'
56 Meter	\$145.00	\$2.75	5 HR	184'	167'
58 Meter	\$160.00	\$3.00	8 HR	188'	175'
61 Meter	\$200.00	\$4.00	8 HR	197'	185'

CONVEYOR BELTS

	Pump/Hr.	CY/Price	Min.Pump Chg
105'	\$100.00	\$2.50	5 HR
130'	\$120.00	\$2.50	5 HR

Boom Pump Operator Rates	0-8 hrs.	8-12 hrs	12 hrs+
Operator	\$120.00	\$170.00	\$211.00
Oiler	\$113.00	\$158.00	\$196.00

Operators and oilers have a 4 & 8 hour minimum which includes 1-hour set up and 1-hour clean up time and will be charged in accordance with the California State Labor Laws. All pumps have a 1-hr setup and 1-hr washout. Labor rates are subject to change July 1, 2016. A \$40 CARB fee will be charged to each pour. Overtime will be charged over 8 hour days, weekends and holidays. Pours before 2am or after 4pm, will be charged at overtime rates. Labor prices are subject to change July 1, 2015. Pours requiring more than 50' of system will be charged \$2.00/per foot over 50'. A 8% energy sur-charge will be charged to all pours.

Oiler is required on 42 thru 61 meter booms, or when the operator cannot see the point of pour from on, or at the pump.

In the event of a mechanical failure, a 1 hour grace period will be required.

TRAILER PUMPS

HARD ROCK PUMP RATES:

\$320.00 setup, 3 hr. min., includes 1 hr. setup and 1 hr. cleanup, plus \$8.00 per cubic yd. Additional time charged @ \$90.00 per hr. after the 3 hr. minimum. [Additional time charged includes operator & pump.] System over 150' is charged @ \$2.00 per foot. 4" hose will be charged \$2.00/per foot. **Prevailing wage rates:** \$40.00 per hr., plus operator (and 2nd man if needed) at respective rates [see above] 1 hr. setup, 1 hr. cleanup with a 4 hr. min. + \$1.75 per cubic yd. A 5% energy sur-charge will apply to all pours.

PEA GRAVEL PUMP RATES:

\$185.00 setup, 2 hr. min., includes 1/2 hr. setup and 1 hr. cleanup, plus \$8.00 per cubic yd. Additional time charged @ \$60.00 per hr. after 2 hours. [Charges include operator & pump.] System over 200' is charged @ \$1.00 per foot. **Prevailing wage rates:** \$35.00 per hr., plus operator at respective rates [see above] 1/2 hr. setup, & 1 hr. cleanup with a 4 hr. min. + \$1.75 per cu. yd. A 5% energy sur-charge will apply to all pours.

Proposed by: Chuck Reed 760-889-1534 Title: President