

PART 1 GENERAL**1.1 MOCK-UP TOILET ROOM**

- A. "Mock-Up" Toilet Room referred to in this section will be of permanent construction as part of the building in a location (Men or Women) selected by Contractor and approved by Architect and Owner before starting.
1. Before starting the work of this section, review the requirements for "plywood mock-up" of lavatory countertop/Division 12 Section "Stone Countertops".
- B. One "Mock-up" Toilet Room complete with all finishes and accessories representing "ready for occupancy" is required before proceeding in other areas with the various types of work required to complete this room. This "mock-up" room work requires but is not limited to the following:
1. Gypsum board walls complete with ceramic tile work, cleaned.
 2. Ceiling of type scheduled including all trim.
 3. Ceramic tile floors, cleaned.
 4. Door frame and door of type scheduled including hardware.
 5. Lavatory counters with lavatories, lavatory trim and mirrors.
 6. Toilet partitions.
 7. Toilet and related accessories.
 8. Operating lights.
 9. Toilet fixtures and accessories.
 10. Air diffusers.
 11. Paint.
 12. Floor drains.
 13. Access doors.
- C. After Architect's and Owner's acceptance of "Mock-up" Toilet Room, the types of work required to complete this room can proceed in other areas by using this "mock-up" room as minimum requirements for the work.

1.2 MOCK-UP OF BACKLIT LIGHT BOX ASSEMBLIES AT GROUND FLOOR ELEVATOR LOBBY

- A. This mock-up shall be of the extent of construction indicated on Drawing 2A91.13 and A91.04. Mock-up shall include but not be limited to the following:
1. Specialty Resin Panels.
 2. Operating light fixtures.
 3. Stainless steel trim and panels.
 4. Elevator hoistway entrance head and jamb frame.
 5. Backup and adjacent construction for light boxes, including painted gypsum board.
 6. Stone.
- B. Intent of mockup is to show the following:
1. Indicator light, head and jamb intersection of elevator opening and transom light, stainless steel accent, and stone wall.
 2. Ceilings light to transom light above elevator.
- C. Mockup shall include 5 versions of specialty resin panel material to be studied with the lighting. Coordinate with lighting lockup requirements specified in Architectural Lighting specifications.
- D. After Architect's and Owner's acceptance of "Mock-up", the types of work required to complete this work can proceed in other areas by using this "mock-up" as minimum requirements for the work.

1.3 MOCK-UP OF LOBBY STONE/STAINLESS STEEL WALL

- A. This mockup shall be of the extent of construction indicated drawing 2A91.01. Mockup shall include but not be limited to the following.
1. Stone including fastening systems.
 2. Metal subframes, including fastening systems.
 3. Stainless steel cladding.
 4. Backup support wall.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

END OF SECTION