

Addendum #1

After seeing the piping in progress of being installed on the platform Plant Operations has serious concerns. They have determined that to make future shut-down work and operations functional they would like to see high point vents installed at all high points in the piping on the deck for instrument air, utility air, main gas and waste water production fluid. Please provide pricing to provide labor, equipment, and supervision to install a welded ¾" o-let, nipple, and gate valve at all locations required. For material type follow the piping class of the line that it's being installed on. All material is provided. Please note the pricing adder on the bid form.