



GENERAL NOTES

1. REFER TO M-001 FOR MECHANICAL ABBREVIATIONS, LEGEND, SYMBOLS, AND GENERAL NOTES.
2. COMPONENTS SHOWN DASHED ON THIS DRAWING ARE ITEMS TO BE DEMOLISHED; HALF-TONE COMPONENTS ARE EXISTING-TO-REMAIN.
3. PRIOR TO ANY DEMOLITION ACTIVITIES, SUBCONTRACTOR MUST COORDINATE WITH THE STR TO REVIEW FACILITY ES&H DOCUMENTS, EQUIPMENT TO BE REMOVED, MATERIALS TO BE REMOVED OR DISTURBED, AND IDENTIFY A PLAN PRIOR TO COMMENCING THE WORK. ITEMS TO REVIEW INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: NEW WORK IN DISTURBING EXISTING WALLS, FLOORS, ROOFS, OR CEILINGS; ALL CUTTING OR DRILLING; ALL DEMOLITION; REMOVAL AND DISPOSAL.
4. CUT, REMOVE, AND LEGALLY DISPOSE OF ALL MECHANICAL ITEMS SELECTED FOR DEMOLITION AND ANY MECHANICAL ITEMS MADE OBSOLETE BY THE NEW WORK, INCLUDING EXISTING EQUIPMENT/PIPE/TUBE SUPPORTS AND HANGERS.
5. REFER TO STRUCTURAL AND CIVIL DRAWINGS FOR SITE DEMOLITION REQUIRED TO SUPPORT INSTALLATION OF NEW HVAC EQUIPMENT.
6. NEW DUCTWORK MUST BE INSTALLED PRIOR TO DEMOLITION OF EXISTING DUCTWORK TO LIMIT DURATION OF SYSTEM OUTAGE. REFER TO M-403.

KEYED NOTES

- 1 REMOVE AND DISPOSE OF EXISTING DUCTWORK WALL PENETRATION. INFILL WALL PENETRATION AND SEAL PER ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. REFER TO A-501.
- 2 REMOVE AND DISPOSE OF EXISTING SUPPLY AIR DISTRIBUTION DUCTWORK BELOW CEILING INCLUDING: AIR TERMINALS, SUPPORTS, ANCHORAGE, AND APPURTENANCES.
- 3 REMOVE AND DISPOSE OF EXISTING GRILLE PENETRATION THROUGH WALL. INFILL WALL PENETRATION AND SEAL PER ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. REFER TO A-501.
- 4 REMOVE AND DISPOSE OF EXISTING RETURN AIR DUCTWORK TO SECOND FLOOR INCLUDING: AIR TERMINALS, SUPPORTS, ANCHORAGE, AND APPURTENANCES.
- 5 REMOVE AND DISPOSE OF EXISTING WALL-MOUNTED THERMOSTAT. REMOVE AND DISPOSE OF EXISTING THERMOSTAT, WIRING, AND CONDUIT FROM DEVICE TO ASSOCIATED ACHPS UNIT.

KEY PLAN

Sheet Title

MECHANICAL ENLARGED 1ST FLOOR HIGH BAY DEMOLITION PLAN - DUCTWORK

Dwg. No.
PLM2021-0432-0008D

Sht. No.
MD403