



- GENERAL NOTES**
1. REFER TO M-001 FOR MECHANICAL ABBREVIATIONS, LEGEND, SYMBOLS, AND GENERAL NOTES.
  2. COMPONENTS SHOWN DASHED ON THIS DRAWING ARE ITEMS TO BE DEMOLISHED; HALF-TONE COMPONENTS ARE EXISTING-TO-REMAIN.
  3. PRIOR TO ANY DEMOLITION ACTIVITIES, SUBCONTRACTOR MUST COORDINATE WITH THE STR TO REVIEW FACILITY ES&H DOCUMENTS, EQUIPMENT TO BE REMOVED, MATERIALS TO BE REMOVED OR DISTURBED, AND IDENTIFY A PLAN PRIOR TO COMMENCING THE WORK. ITEMS TO REVIEW INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: NEW WORK IN DISTURBING EXISTING WALLS, FLOORS, ROOFS, OR CEILINGS; ALL CUTTING OR DRILLING; ALL DEMOLITION; REMOVAL AND DISPOSAL.
  4. CUT, REMOVE, AND LEGALLY DISPOSE OF ALL MECHANICAL ITEMS SELECTED FOR DEMOLITION AND ANY MECHANICAL ITEMS MADE OBSOLETE BY THE NEW WORK, INCLUDING EXISTING EQUIPMENT/PIPE/TUBE SUPPORTS AND HANGERS.
  5. NEW DUCTWORK MUST BE INSTALLED PRIOR TO DEMOLITION OF EXISTING DUCTWORK TO LIMIT DURATION OF SYSTEM OUTAGE. REFER TO M-402, M-405, AND M-407.

- KEYED NOTES**
- ① REMOVE AND DISPOSE OF EXISTING DUCTWORK THROUGH ROOF. INFILL EXISTING ROOF OPENINGS EXPOSED BY REMOVAL OF ROOFTOP ACHPS UNIT AND SEAL WATER TIGHT PER ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS. REFER TO F3 / A-501 AND S-512.
  - ② REMOVE AND DISPOSE OF EXISTING DISTRIBUTION DUCTWORK BELOW CEILING INCLUDING: AIR TERMINALS, SUPPORTS, ANCHORAGE, AND APPURTENANCES.
  - ③ REMOVE AND DISPOSE OF EXISTING RETURN AIR PLENUM BELOW CEILING INCLUDING: AIR TERMINALS, SUPPORTS, ANCHORAGE, AND APPURTENANCES.
  - ④ EXISTING DUCT SMOKE DETECTOR. RETAIN AND RE-INSTALL ON REPLACEMENT ACHPS SYSTEM. REFER TO M-403 AND M-405.
  - ⑤ REMOVE AND DISPOSE OF WALL-MOUNTED THERMOSTAT AND WIRING AND CONDUIT FROM DEVICE TO ROOF-MOUNTED (D)ACHPS01. PATCH AND PAINT WALLS WHERE DEMOLITION RESULTS IN UNFINISHED CONDITION.

KEY PLAN

MECHANICAL ENLARGED 2ND FLOOR OPEN OFFICE DEMOLITION PLAN - DUCTWORK

Dwg. No. PLM2021-0432-0009D

Sht. No. MD404