Build a Schedule

Instructions:

- Start date is Monday, February 13, 2017
- Owner wants to be 100% moved in & operational by end of January 2018
- Sequence and include the below milestones in your schedule Add any other milestones you see necessary
- At a minimum the below activities need to be in your schedule Add any other activities you see necessary
- Schedules need to be at least 150 line items
- We are grading based on quality not quantity of line items in your schedule
- This schedule should be built using the information found on the plans provided. Understand the type of structure this is and what elements go into the building to develop a *project specific* schedule.

Please turn in your schedule by printing to PDF!

- Use "smartsheet" to build your schedule, see the attached instructions for how to access and use the program.
- Make sure that the following columns are shown in your PDF
 - Activity Names
 - Durations
 - Start & Finish Dates
 - Activity Bars

Milestones:

- Building Demolition
- Certificate of Occupancy
- Demolition Permit
- East Skin System
- Mechanical Yard
- Shell City Submittal
- Shell Permit
- Site Improvements
- West Skin System

- Start Shell Construction
- Start TI Construction
- Steel Procurement
- Substantial Completion
- Substructure
- Superstructure
- TI City Submittal
- TI Permit

Activities:

- Air balance
- carpet
- Casework
- ceiling grid
- connect to site utilities
- curtain wall skin
- Demolish existing building
- drop ceiling tiles

- drywall
- epoxy flooring
- Erect structural steel
- Excavation
- exterior framing
- Flooring base
- Fly roof equipment
- Infill tilt up concrete panel openings with skin system

- Inspect elevator
- Install haz mat shed
- Install lobby stair
- Install mech yard CMU
- Install racks in server room
- interior framing
- MEP fixtures
- Metal decking

- overhead MEPF
- painting
- Place concrete foundations

- Rebar foundations
- reclaimed wood flooring
- resilient flooring

- roofing
- SOMD

- start elevator install
- Startup/ commission MEP equipment
- tape & mud drywall
- tile
- Toilet partitions
- Venetian plaster