© 2007 FKP Architects, Inc. All rights reserved. No part of this document may be reproduced or utilized in any form without prior written authorization of FKP Architects, Inc.

No.	Unit #	Equipment	Length In.	Width In.	Height In.	Weight Lbs. (U.N.O.)	Location	Detail
197	1034	Anesthesia Machine	-	-	-	366	-	N/A
198	1322	Cart	-	-	-	140	-	N/A
199	6270	Cart	-	-	-	145	Mobile/Wall	D5/A11.8
200	12097	Medrad Injector	-	-	-	112	Ceiling	A4/S3
201	12109	X-Ray Unit	-	-	-	869	Mobile/Wall	A5/S3.3
202	12901	Ultrasound Imaging	-	-	-	406	Mobile/Wall	D5/A11.8
203	14296	Safe	-	-	-	2746	Floor	B4/S3.10
204	16220	Refrigerator	-	-	-	1,600	Floor	A4/S3.6
205	19331	Cart	-	-	-	350	Mobile/Wall	D5/A11.8
206	Not Used							
207	Not Used							
208	Not Used							
209	Not Used							
210	Not Used							
211	30609	Cart	-	-	-	-	Mobile/Wall	A4/S3.11
212	Not Used							
213	A0052	Shelving	-	-	-	-	Floor	B4/S3.13
214	16128R1	Cart	-	-	-	400	-	N/A
215	16128R	Cart	-	-	-	400	-	N/A
216	M110	Wall Mount Channel	-	-	-	60	Wall	D4/S3.4
217	A0080	Cart	-	-	-	69	Mobile/Wall	A5/A11.8
218	A0115	Cart	-	-	-	-	Mobile/Wall	A5/A11.8
219	A0121	Cart	-	-	-	-	Mobile/Wall	A5/A11.8
220	Not Used							
221	Not Used							
222	Not Used							
223	L541	-	-	-	-	54	Counter	D1/S3.13
224	Not Used							
225	Not Used							
226	X484	Magnetom Espree MRI	-	-	-	11244	Floor	B2/S5.1
227	Not Used							
228	X484	Electronic Cabinets	-	-	-	2755	Floor-Wall	D1/S3.11
229	X484	RF Filter Plate	-	-	-	286	Wall	B4/S3.11
230	X484	Sep Cabinet	-	-	-	750	Floor-Wall	D1/S3.11
231	19848	Warming Cabinet	-	-	-	254	Wall	D2/S3.3
232	19168	Crib	-	-	-	210	Mobile/Wall	D5/A11.8
233	Not Used							
234	M715 & M716	Ota/Opthalmoscope set	-	-	-	26	Wall	T.B.D.
235	1032	Anesthesia Machine	-	-	-	365	-	N/A
236	Not Used							
237	Not Used							
238	13600	Ablation system	-	-	-	289	Mobile/Wall	A5/S3.3
239								
240								
241	16100R	Automated Dispensing station	-	-	-	1050	Floor	B1/S3.11
242	16125R	Dispenser, Supply	-	-	-	2920	Floor	B1/S3.11
243	Not Used							
244	16130R	Dispenser, Supply	-	-	-	2920	Floor	B1/S3.11
245	16131R	Dispenser, Supply	-	-	-	2920	Floor	B1/S3.11
246	16133R & 16113R1	Dispenser, Supply	-	-	-	1460	Floor	B1/S3.11
247	16134R	Dispenser, Supply	-	-	-	1460	Floor	B1/S3.11
248	16135	Dispenser, Supply	-	-	-	1460	Floor	B1/S3.11
249	21042	Rapid point 500	-	-	-	40	Counter	D1/S3.13
250	Not Used							
251	Not Used							
252	Not Used							
253	Not Used							
254	Not Used							
255	BRK0085	Monitor Bracket	-	-	-	50	Ceiling	B5/S3.11
256	Not Used							
257	X249	Single Rack Cabinet	-	-	-	243 or 882	Floor	A2/S3.1
258	X249	PCDU-100VL Distribution Unit	-	-	-	700	Floor	A5/S3.8
259	X249	Double Rack Cabinet	-	-	-	993	Floor	A5/S3.4
260	X249	DFP-8000 Computer Cabinet	-	-	-	375	Floor	D1/S3.4
261	X249	HEX-125 Cooling Unit	-	-	-	200 max.	Rack	T.B.D.

No.	Unit #	Equipment	Length In.	Width In.	Height In.	Weight Lbs. (U.N.O.)	Location	Detail
262	X249	FPD Coolant Circulator & DFP-8000D Box	-	-	-	200 max.	Floor	B5/S3.10
263	X249	CAT-820B Table	-	-	-	1,544	Floor	B1/S3.4 sim.
264	X249	CAS-820 Suspension	-	-	-	2,626	Ceiling	C1/S2.3
265	X249	CAS-880 C-Arm	-	-	-	2426	Floor	B2/S3.7
266	19164	Bed, Electric				420	Mobile	N/A
267	X485	Magetom Skyra (MRI)	-	-	-	15652	Floor	A2/S5.1
268	X485	Patient Table (fixed)	-	-	-	1080	Floor	A2/S5.1
269	X485	RF Filter Plate	-	-	-	287	Wall	B4/S3.11
270	X484C	Console, MRI				132	Counter	T.B.D.
271	X485	Electronics Cabinet	-	-	-	3307	Wall-Floor	D1/S3.11
272	X485	SEP Cabinet	-	-	-	750	Wall-Floor	D1/S3.11
273	M715	Oto/Opthalmoscope	-	-	-	<20	Wall	-
274	19730	Stadiometer	-	-	-	<20	Wall	-
275	A0147	Cabinet, Storage	-	-	-	<20	Wall	-
276	A0097	Cabinet, Security	-	-	-	<400	Floor	-
277	2346	Treadmill	-	-	-	<400	Floor	-
278	2347	Treadmill	-	-	-	<400	Floor	-
279	23325	Incubator	-	-	-	<400	Floor	-
280	A0063	Cabinet, Security	-	-	-	<400	Floor	-
281	Not Used							
282	Not Used							
283	16101	Dispensor, Medication	-	-	-	101	Counter	D1/S3.13
284	20165	Bath, Thawing	-	-	-	74	Counter	D1/S3.13
285	20162	Bath, Water	-	-	-	39	Counter	D1/S3.13
286	20237	Centifuge, Refigerated	-	-	-	225	Counter	D1/S3.13
287	20578	Analyizer, Lab	-	-	-	217	Counter	D1/S3.13
288	21027A	Analyizer, Lab	-	-	-	351	Counter	D1/S3.13
289	23070	Analyizer, Lab	-	-	-	240	Counter	D1/S3.13
290	23285	Washer, Microplate	-	-	-	30	Counter	D1/S3.13
291	24001	Stainer, Slide	-	-	-	330	Counter	D1/S3.13
292	21360	Refrigerator, Blood Bank	-	-	-	950	Floor	A4/S3.6
293	20706	Refrigerator, Lab	-	-	-	1,600	Floor	A4/S3.6
294	16221	Refrigerator, Lab	-	-	-	1,600	Floor	A4/S3.6
295	20751	Freezer, Ultra Low	-	-	-	950	Floor	A4/S3.6
296	Not Used							
297	3209	X-ray Machine	-	-	-	81	Floor	T.B.D.
298	13722	Navigation System	-	-	-	580	Floor	T.B.D.
299	13723	Navigation System	-	-	-	580	Floor	T.B.D.
300	Not Used							
301	16222	Refrigerator	-	-	-	<400	-	-
302	A0059	Shelving w/ track	-	-	-	20 (per cubic ft.)	Floor	B1/S3.13
303	A0061	Stationary Wire Shelving Anchorage	-	-	-	1600	Floor	B4/S3.13
304	Not Used							
305	A0064	Stationary Wire Shelving Anchorage	-	-	-	2000	Floor	B4/S3.13
306	Not Used							
307	Not Used							
308	A0067	Stationary Wire Shelving Anchorage	-	-	-	1050	Floor	B4/S3.13
309	A0068	Stationary Wire Shelving Anchorage	-	-	-	878	Mobile/Wall	A4/S3.11
310	A0070	Stationary Wire Shelving Anchorage	-	-	-	1420	Mobile/Wall	A4/S3.11
311	A0071	Shelf	-	-	-	150	Wall	B2/S3.13
312	A0072	Stationary Wire Shelving Anchorage	-	-	-	799	Floor	B4/S3.13
313	A0074	Stationary Wire Shelving Anchorage	-	-	-	2400	Floor	B4/S3.13
314	Not Used							
315	A0076	Stationary Wire Shelving Anchorage	-	-	-	1200	Floor	B4/S3.13
316	A0078	Stationary Wire Shelving Anchorage	-	-	-	1350	Floor	B4/S3.13
317	A0079	Stationary Wire Shelving Anchorage	-	-	-	2000	Floor	B4/S3.13
318	A0080	Stationary Wire Shelving Anchorage	-	-	-	1050	Floor	B4/S3.13
319	A0081	Stationary Wire Shelving Anchorage	-	-	-	1200	Floor	B4/S3.13
320	Not Used							
321	A0085	Stationary Wire Shelving Anchorage	-	-	-	1110	Floor	B4/S3.13
322	Not Used							
323	A0088	Stationary Wire Shelving Anchorage	-	-	-	1035	Floor	B4/S3.13

No.	Unit #	Equipment	Length In.	Width In.	Height In.	Weight Lbs. (U.N.O.)	Location	Detail
324	A0090	Stationary Wire Shelving Anchorage	-	-	-	439	Mobile/Wall	A4/S3.11
325	A0091	Stationary Wire Shelving Anchorage	-	-	-	625	Floor	B4/S3.13
326	A0093	Shelving w/ track	-	-	-	1067	Floor	A1/S3.13
327	A0094	Shelving w/ track	-	-	-	20 (per cubic ft.)	Floor	A1/S3.13
328	A0096	Shelving w/ track	-	-	-	20 (per cubic ft.)	Floor	A1/S3.13
329	A0115	Stationary Wire Shelving Anchorage	29	26	62	812	Mobile/Wall	A4/S3.11
330	A0116	Stationary Wire Shelving Anchorage	36	18	77	866	Floor	B4/S3.13
331	A0117	Stationary Wire Shelving Anchorage	60	18	80	1500	Floor	B4/S3.13
332	Not Used							
333	A0120	Stationary Wire Shelving Anchorage	48	24	80	1600	Floor	B4/S3.13
334	20241	Centrifuge Anchorage	-	-	-	-	Floor	A1/S3.14
335	A0109	Mass Spectrophotometer	-	-	-	-	-	T.B.D.
336	A0112	Refrigerator	-	-	-	<400	-	-
337	A0166	Detector	-	-	-	<20	-	-
338	07046	Analyzer	-	-	-	120	Counter	D1/S3.13
339	21200	Washer Cell	-	-	-	34	Counter	D1/S3.13
340	21205	Slide Stairer	-	-	-	33	Counter	D1/S3.13
341	21019	Analyzer	-	-	-	50	Counter	D1/S3.13
342	20753	Refrigerator	-	-	-	950	Floor	A4/S3.6
343	20583	-	-	-	-	<400	-	-
344	A0040	Analyzer	-	-	-	125	Counter	D1/S3.3
345	16222 16121	Refrigerator	-	-	-	<400 <400	-	-
346	R607	Refrigerator	-	-	-	<400	-	-
347	R613	Refrigerator	-	-	-	<400	-	-
348	R619HR	Refrigerator	-	-	-	1100	Floor	B5/S3.5
349	16110 16101R	Dispenser	-	-	-	101	Counter	D1/S3.13
350	6307	Sterilizer	-	-	-	150	Counter	D1/S3.13
351	21367	Freezer	-	-	-	950	Floor	A4/S3.6
352	06618R	Refrigerator	-	-	-	1100	Floor	B5/S3.5
353	24050	Tissue System	-	-	-	110	Counter	D1/S3.13

FKP Architects

ARCHITECT OF RECORD

"Achitect of Record signature line only; this drawing was not prepared under the direct supervision of the Architect of Record. The direct responsibility for preparation of this sheet lies with its corresponding professional stamp and signature. The signature of the Architect of Record in general responsible charge of the project is provided as required by Title 24, Part 1, Section 7-115 (a)".

ARCHITECT - PAUL C. GLORIOD

Changes on these drawings do not consist of materially altered changes to approved drawings and don't require a change order.
OSHPD review ACO _____
OSHPD review FLSO _____
OSHPD review DSE _____

CONSULTANT

TMAD TAYLOR & GAINES
• STRUCTURAL
• MECHANICAL
• ELECTRICAL
• CIVIL

320 North Halstead Street, Suite 200
Pasadena, California 91107
Phone: 626.351.8881
Fax: 626.351.5319
Project No. 4206.075

REGISTERED PROFESSIONAL ENGINEER EDMOND T GHARAKHANIAN No.2942 Exp. 06/30/13 STRUCTURAL STATE OF CALIFORNIA

REVISIONS
Refer to sheet S0 for revisions not noted

1	11/09/11	OSHPD Change Order 264
2	01/04/12	OSHPD Change Order 271
3	01/18/12	OSHPD Change Order 272
4	04/09/12	ASI #198
5	05/30/12	OSHPD Change Order 364
6	06/06/12	OSHPD Change Order 379
7	06/13/12	OSHPD Change Order 381
8	08/01/12	OSHPD Change Order 387
9	09/05/12	OSHPD Change Order 404

APPROVAL

PAR 2012-08219
REVIEWED IN ACCORDANCE WITH THE REQUIREMENTS OF T24, CCR
APPROVED
9-5-12
Date
Office of Statewide Health Planning & Development
FACILITIES DEVELOPMENT DIVISION

PROJECT NAME

CHILDREN'S HOSPITAL OF ORANGE COUNTY
455 S. Main St.
Orange, CA 92868-3874

TOWER II

CHOC HOSPITAL

PROJECT NUMBER

12011.00
Increment #7

OSHPD - PROJECT NUMBER

IL 072072-30

ISSUE

OSHPD Permit

DATE

01/28/2010

SCALE

NONE

DRAWING TITLE

MEDICAL EQUIPMENT SCHEDULE

DRAWING NUMBER

S0.2

R:\42CAD\TGProjects\4206_Projects\4206.075\Medical Equipment_Sheet\Archive\SUBMITTALS\2012-09-05_OSHPD CO#404\DWG\4206075_S0.2.dwg Tue, 04 Sep, 2012 - 8:34am Plotted by: rcarrasco