

ROOM AIR BALANCE TABLE LEVEL - TOWER II - THIRD LEVEL SOUTH CONTINUED

ROOM NUMBER/NAME	ROOM AREA (FT.) ²	CEILING HEIGHT (FT.)	CMC		PRESSURE +/-	OSA AC/HR	SUPPLY CFM	RETURN CFM	EXHAUST CFM	INFILTRATION CFM	EXFILTRATION CFM
			AC/HR.	REQUIRED SUPPLY AC/HR.							
3.106.01 TLT Patient	53	9	6	48	E	2	50	0	150	100	0
3.106.04 Procedure GI/Endo	313	9	12	563	N	6	1,000	0	1,150	150	0
3.106.06 Procedure GI/Endo	268	9	12	482	N	7	1,000	0	1,150	150	0
3.106.08 Procedure	324	9	12	583	N	6	1,000	0	1,150	150	0
3.106.02 Exam Motility Urodynamic	250	9	6	225	E	4	500	0	500	0	0
3.108 Storage Life Child	159	9	4	95	E	3	200	200	0	0	0
3.107 Storage Equipment	89	9	4	53	E	2	100	100	0	0	0
3.106.09 Soiled Work Room	146	9	4	88	E	3	200	0	300	100	0

ROOM AIR BALANCE TABLE LEVEL - PANCAKE - LEVEL 3 NORTH

ROOM NUMBER/NAME	ROOM AREA (FT.) ²	CEILING HEIGHT (FT.)	CMC		PRESSURE +/-	OSA AC/HR	SUPPLY CFM	RETURN CFM	EXHAUST CFM	INFILTRATION CFM	EXFILTRATION CFM
			AC/HR.	REQUIRED SUPPLY AC/HR.							
3.001.48 Toilets Male & 3.001.48A LOCKERS	540	9	10	810	N	3	700	0	850	150	0
3.001.46 Pharmacy	617	9	6	555	P	9	2,800	2650	0	0	150
3.046.05 Toilet Staff	65	9	10	98	N	2	75	0	150	75	0
3.001.46.C Hall	562	9	4	337	E	1	400	475	0	150	75
3.066 Electrical Room	53	9	4	32	E	19	500	500	0	0	0
3.064 IS Room	57	9	4	34	E	44	1,250	1250	0	0	0
3.001.52 Lounge M.D.	296	9	4	178	E	4	600	0	800	0	0
3.001.50 Lounge Staff	505	9	4	303	E	4	1,000	0	1,000	0	0
3.046.06 Housekeeping	98	9	10	147	N	2	100	0	200	100	0
3.046.00.G PACU 6	126	9	6	113	E	3	200	0	200	0	0
3.046.00.H PACU 5	124	9	6	112	E	3	200	0	200	0	0
3.046.04.A Alcove Equip	95	9	4	57	E	3	150	0	150	0	0
3.046.00.O PACU 7	130	9	6	117	E	3	200	0	200	0	0
3.046.00.P PACU 8	132	9	6	119	E	3	200	0	200	0	0
3.046.07 Storage Equipment	90	9	4	54	E	3	150	0	150	0	0
3.001.02.C Corridor	71	9	4	43	E	4	150	0	150	0	0
3.046.12A Nurse station & 3.046.03C Hall	1400	9	4	840	E	2	1,300	1125	0	0	175
3.046.00.D.E & F PACU 16.17 & 18	348	9	6	313	E	3	450	0	450	0	0
3.046.00.A.B & C PACU 13.14 & 15	348	9	6	313	E	3	450	0	450	0	0
3.046.08A Nurse station, 3.046.04C, 3.046.01C, 3.046.02C HALL	1638	9	4	983	E	2	1,300	1225	0	150	225
3.046.01 Point Of Care	127	9	4	76	E	5	300	0	300	0	0
3.046.02 Toilet Patient	53	9	10	80	N	4	100	0	150	50	0
3.046.09 Nourishment	104	9	4	62	E	6	300	300	0	0	0
3.046.10 Meds Station	126	9	4	76	P	5	300	250	0	0	50
3.046.08 Clean Linen/ Utility	226	9	6	203	P	4	450	350	0	0	100
3.046.00.Q PACU 9	101	9	6	91	E	4	200	0	200	0	0
3.046.00.R PACU 10	109	9	6	98	E	4	200	0	200	0	0
3.046.11 Soiled Workroom	79	9	10	119	N	5	200	0	300	100	0
3.046.00M PACU 11	127	9	6	114	E	3	200	0	200	0	0
3.046.00N PACU 12	127	9	4	76	E	3	200	0	200	0	0
3.046.03 Toilet Patient	46	9	10	69	N	3	75	0	150	75	0
3.046.00L PACU 1	147	9	6	132	P	3	200	0	200	0	0
3.046.00I PACU 4	125	9	6	113	E	3	200	0	200	0	0
3.046.00K Air born Infection Isolation Room PACU 2	126	9	12	227	N	5	300	0	400	100	0
3.046.00J Air born Infection Isolation Room PACU 3	126	9	12	227	N	5	300	0	400	100	0
3.046.04 Anti Room	48	9	12	86	P	8	200	0	0	0	200
3.001.01.C Corridor	359	8.5	4	203	E	1	200	0	200	0	0
3.036.00.C Corridor	659	9	4	395	E	2	500	0	400	0	100
3.001.34 Anesth. Workroom	209	9	4	125	E	3	300	0	300	0	0
3.001.36 Equipment, Anesthesia	179	9	8	215	E	3	300	0	300	0	0
3.001.38 Storage, Cylinder	79	9	4	47	E	3	100	0	100	0	0
3.001.40 Housekeeping	117	9	10	176	N	2	100	0	200	100	0
3.040.00.V Vestibule	70	9	4	42	E	4	150	0	150	0	0
3042 Electrical Room	85	9	4	51	E	24	1,000	0	1,000	0	0

ROOM AIR BALANCE TABLE LEVEL - PANCAKE LEVEL 3 SOUTH

ROOM NUMBER/NAME	ROOM AREA (FT.) ²	CEILING HEIGHT (FT.)	CMC		PRESSURE +/-	OSA AC/HR	SUPPLY CFM	RETURN CFM	EXHAUST CFM	INFILTRATION CFM	EXFILTRATION CFM
			AC/HR.	REQUIRED SUPPLY AC/HR.							
3.001.01.C Corridor	1077	8.5	4	610	E	1	600	0	820	420	200
3.001.37 CVOR	664	9.5	20	2,103	P	13	4,500	4150	0	0	350
3.001.35 Perfusion Workroom & EQ	219	9	4	131	E	5	500	500	0	0	0
3.001.33 Soiled Holding	90	9	10	135	N	4	200	0	250	50	0
3.001.31 CVOR	650	9.5	20	2,058	P	13	4,500	4150	0	0	350
3.001.29 Sterile Core (Use Clean Work Room)	1444	9	6	1,300	N	2	1,300	0	2,250	1,050	100
3.001.08.C Corridor and Alcove Scrub 3.001.33A	931	9	4	459	E	1	400	0	600	200	0
3.001.27 OR	609	9.5	20	1,929	P	8	2,520	2150	0	0	370
3.001.25 OR	626	9.5	20	1,982	P	8	2,520	2150	0	0	370
3.001.23 Soiled Cart	120	9	10	180	N	4	250	0	300	50	0
3.001.21 OR, Ortho	626	9.5	20	1,982	P	8	2,520	2150	0	0	370
3.001.05.C Corridor and Alcove Scrub 3.001.25A	1542	8.5	4	874	E	1	950	0	1,730	880	100
3.001.28.B Soiled Holding	159	9	10	239	E	3	250	0	300	50	0
3.001.28.C Storage Equipment	427	9	4	256	E	2	350	0	350	0	0
3.001.26 Storage/Equip, Ortho	153	9	4	92	E	3	250	0	250	0	0
3.024 Electrical Room	136	9	4	82	E	15	1,000	0	1,000	0	0
3.022 IS Room	137	9	4	82	E	18	1,250	0	1,250	0	0
3.001.24 Storage, Equipmnet	274	9	4	164	E	2	300	0	300	0	0
3.001.22 Storage General	185	9	4	111	P	3	250	0	250	0	0
3.001.16 Shell	2037	9	12	3,667	P	6	1,000	0	1,000	0	0
3.001.10 Storage Equipment	119	9	4	71	E	3	200	0	200	0	0
3.001.04.C Corridor	270	9	4	162	E	1	200	0	200	0	0
3.001.19 OR	629	9.5	20	1,992	P	8	2,520	2150	0	0	370
3.001.07.D Cath Lab #2 Equipment Room	582	8.5	4	330	E	8	400	0	720	420	0
3.001.07.C Cath Lab #2 Equipment Room	330	9	4	198	E	1	400	0	136	210	0
3.001.07 Control	330	9	4	198	E	1	400	0	136	210	0
3.001.07A Storage/Supply	133	9	4	80	N	5	350	1100	0	750	0
3.001.17 Cath Lab #2	791	9.5	20	2,505	P	7	3,080	2460	0	0	620
3.001.05 Hybrid Cath Lab	902	9	20	2,706	P	7	3,080	2580	0	0	500
3.001.05A Pump Support	75	9	4	45	E	7	600	0	700	100	0
3.001.03 Hybrid Electronic	110	9	4	66	E	18	250	0	300	50	0
3.001.01 Toilet/ Female/ 3.001.01A Lockers	594	9	10	891	N	3	1,000	0	1,200	200	0
3.001.03.C Corridor	889	9	4	533	E	1	600	0	450	0	150
3.001.08 Work Station CATH Staff	116	9	4	70	E	3	200	0	200	0	0
3.109.21 Staff Toilet	45	9	10	68	N	3	75	0	150	75	0
3.001.06 Storage Cath	85	9	4	51	E	9	400	0	400	0	0
3.001.04 Office CATH Manager	86	9	4	52	E	5	200	0	200	0	0
3.001.02 House Keeping	82	9	10	123	N	3	125	0	200	75	0
3.001.00.C Corridor	212	9	4	127	E	3	300	0	0	0	300
3.001.39 OR	629	9	20	1,887	P	8	2,520	2150	0	0	370
3.001.41 Frozen Section	210	9	6	189	N	8	800	0	950	150	0
3.001.43 Office Anesthesia	98	9	4	59	E	3	150	0	0	0	0
3.001.45 Office OR Supervisor	99	9	4	59	E	3	150	0	0	0	0
3.001.32 Sub-Sterile Room	122	9	10	183	P	16	800	0	700	100	0
3.001.30 Clean Utility Room	75	9	10	113	P	27	400	0	300	0	100
3.001.45A OR Control	320	9	4	192	E	2	300	0	325	25	0

ROOM AIR BALANCE TABLE LEVEL - TOWER II - THIRD LEVEL NORTH

ROOM NUMBER/NAME	ROOM AREA (FT.) ²	CEILING HEIGHT (FT.)	CMC		PRESSURE +/-	OSA AC/HR	SUPPLY CFM	RETURN CFM	EX-HAUST CFM	INFILTRATION CFM	EXFILTRATION CFM
			AC/HR.	REQUIRED SUPPLY AC/HR.							
3.084.07 Exam	120	9	6	108	E	3	200	200	0	0	0
3.084.06 Exam	118	9	6	106	E	3	200	200	0	0	0
3.082 Clean Supply Storage	102	9	4	61	P	4	200	150	0	0	50
3.084.05 Exam	132	9	6	119	E	3	200	200	0	0	0
3.084.00.A Work Station Assistant	90	9	6	81	E	4	200	200	0	0	0
3.084.04 Workroom Remote Comm. Center	175	9	6	158	E	5	400	400	0	0	0
3.084.03 Office Mgr.	113	9	4	68	P	4	200	200	0	0	0
3.084.02 Office Future	112	9	4	67	E	4	200	200	0	0	0
3.084.01 Toilet Staff	52	9	10	78	N	3	75	0	150	75	0
3.084.00.C, 3.084.02C, 3.084.01C, 3.089.00C Halls and 3.084.01A & 3.084.02A Alcove	658	9	4	395	E	2	600	525	0	0	75
3.073.00.C Corridor	616	9	4	370	E	1	400	0	400	0	0
3.083.00.C Corridor	165	9	4	99	E	2	150	200	0	50	0
3.084.08 Exam	126	9	6	113	E	3	200	200	0	0	0
3.072.08 Stress Exam	206	9	6	185	E	2	250	250	0	0	0
3.072.06 Exam EKG HOLTER	162	9	6	146	E	2	200	200	0	0	0
3.072.10 Solled Holding	84	9	10	126	N	2	100		175	75	0
3.072.01 Exam Echo	155	9	6	140	E	3	200	200	0	0	0
3.072.03 Exam Echo	155	9	6	140	E	3	200	200	0	0	0
3.072.04 Exam perinatal	209	9	6	188	E	3	300	0	300	0	0
3.072.02 Toilet Patient	70	9	10	105	N	2	75	0	150	75	0
3.072.00.B Tech. Work	78	9	6	70	E	5	200	0	200	0	0
3.072.00.C Holding	234	9	10	351	N	3	400	0	475	75	0
3.072.02.C/3.072.03.C Hall/3.072.00./D3.072.01.A Nurse Work and Weightand											
3.072.01.C Assignment Hall	606	9	4	364	E	1	400	175	0	0	225
3.072 Waiting/3.072.00.A Reception	403	9	6	363	E	2	400	0	400	0	0
3.065 Storage Room	232	9	4	133	E	2	200	0	200	0	0
3.000.00.L Public Elevator Lobby	321	9	4	193	E	3	500	500	0	0	0
3.068.00.L Staff and Patient Lobby	328	9	4	197	E	3	500	0	500	0	0
3.103.00 Corr./3.100.00.B Reception/											
3.100.00.A Wheel Storage	1157	9	4	694	E	1	800	300	0	0	500
3.100.03 Consult	134	9	6	121	E	3	200	200	0	0	0
3.100.02 Public TLT Female	200	9	10	300	N	2	200	0	300	100	0
3.100.01 Public TLT Male	188	9	10	282	N	2	200	0	300	100	0
3.100.04 Consult	169	9	6	152	E	2	200	200	0	0	0
3.109.05.C Corridor	293	9	4	176	E	2	250	125	0	0	125
3.109.35 Staff Toilet	47	9	10	71	N	1	75	0	150	75	0
3.109.37 House Keeping	64	9	10	86	N	2	75	0	150	75	0
3.109.33 TRSH/Linen	123	9	10	185	N	3	200	0	250	50	0
3.109.31 Solled Workroom	97	9	10	146	N	3	200	0	250	50	0
3.109.29 Clean Supply	115	9	4	69	P	1	250	200	0	0	50
3.109.02. Ante Room	47	9	6	42	P	9	200	0	0	0	200
3.109.02.A Iso Prep 1	119	9	12	214	N	5	300	0	400	100	0
3.109.00.0 ISO Prep 2	105	9	12	207	N	5	300	0	400	100	0
3.109.00E Prep 3	121	9	6	109	E	3	200	0	200	0	0
3.109.00F Prep 4	121	9	6	109	E	3	200	0	200	0	0
3.109.02.G Prep 5	177	9	6	159	E	2	200	0	200	0	0
3.109.01.C Corridor and 3.109.01A Alcove Equipment	558	9	4	335	E	1	400	0	400	0	0
3.109.08 Prep 6	150	9	6	135	E	3	250	0	250	0	0
3.109.08 Elec.Rm.	90	9	4	54	E	22	1,000	0	1,000	0	0
3.109.14 Prep 16	141	9	6	127	E	3	200	0	200	0	0
3.109.12 Prep 17	142	9	6	128	E	3	200	0	200	0	0
3.109.10 Prep 18	143	9	6	129	E	3	200	0	200	0	0
3.109.03.C Corridor	349	9	4	209	E	11	250	0	250	0	0
3.109.19 Md work	59	9	6	53	E	6	200	0	200	0	0
3.109.09 Prep 14	134	9	6	121	E	1	200	0	200	0	0
3.109.07 Prep 12	134	9	6	121	E	7	200	0	200	0	0
3.109.27 Prep 11	134	9	6	121	E	3	200	0	200	0	0
3.109.25 Prep 13	134	9	6	121	E	3	200	0	200	0	0
3.109.23 Medication Station	60	9	6	54	P	4	300	0	250	0	50
3.109.16A Nourishment	45	9	6	41	E	4	300	0	400	100	0
3.109.06C Corridor	344	9	4	206	E	8	250	0	150	0	100
3.109.22 Prep 10	135	9	6	122	E	3	200	0	200	0	0
3.109.24 Prep 9	135	9	6	122	E	3	200	0	200	0	0
3.109.26 prep 8	135	9	6	122	E	3	200	0	200	0	0
3.109.28 Prep 7	134	9	6	121	E	3	200	0	200	0	0
3.109.04.C Corr/3.109.17.A Nurse Stn and 3.109.03A Alcove Equipment	1103	9	4	662	E	12	800	0	825	100	75
3.109.18.A Childrens Activity Area	381	9	4	229	E	13	400	0	400	0	0
3.109.20 Prep 15	144	9	6	130	E	0	200	0	200	0	0
3.100.05 Consult	218	9	6	196	E	2	200	200	0	0	0
3.109.01 Toilet Patient	71	9	10	107	N	2	75	0	150	75	0
3.109.16 Toilet Patient	51	9	10	77	N	2	75	0	150	75	0