

Form 2: Bid Schedule

ITEM #	ITEMS OF WORK	BID QTY	UNITS	UNIT PRICES		AMOUNT	
				\$		\$	
151	MOBILIZATION	1	LS				
152	CONSTRUCTION SURVEY AND STAKING	1	FA	700,000	00	700,000	00
153	CONTRACTOR QUALITY CONTROL	1	LS				
	CONTRACTOR QUALITY ASSURANCE	1	FA	900,000	00	900,000	00
156	PUBLIC TRAFFIC	1	LS				
157	SOIL EROSION CONTROL	59	AC				
158	WATERING FOR DUST CONTROL	1,000	HR				
201	CLEARING AND GRUBBING	62	AC				
203	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1	LS				
204.A	ROADWAY EXCVATION	258,489	CY				
204.B	UNCLASSIFIED BORROW	107,579	CY				
204.C	EMBANKMENT CONSTRUCTION	366,068	CY				
204.D	FINISH SLOPES	177,137	SY				
204.E	WASTE	288,080	CY				
205	ROCK BLASTING	507,055	CY				
207	EARTHWORK GEOTEXTILES	6,200	SY				
209	STRUCTURE EXC AND BACKFILL	489	CY				
211	ROADWAY OBLITERATION	43,005	SY				
251	RIPRAP	1	FA	75,000			
301	UNTREATED AGGREGATE COURSE "F"	255,000	SY				
301	UNTREATED AGGREGATE COURSE "D"	201,706	SY				
308	MINOR CRUSHED AGGREGATE	117,100	CY				
401	SUPERPAVE HOT ASPHALT CONCRETE PAVEMENT	177,421	SY				
552	STRUCTURAL CONCRETE	424	CY				
553	PRESTRESSED CONCRETE	8	EA				
556	BRIDGE RAILING	300	LF				
558	WATERPROOFING	3,080	SF				
564	BEARING DEVICES	16	EA				
602.1	CULVERTS AND DRAINS - 24"	6,763	LF				
602.2	CULVERTS AND DRAINS - 30-36"	717	LF				
602.3	CULVERTS AND DRAINS - 48"	163	LF				
602.4	CULVERTS AND DRAINS - 60"	171	LF				
602.5	CULVERTS AND DRAINS - 66"	179	LF				
602.6	CULVERTS AND DRAINS - 72"	229	LF				
602.7	CULVERTS AND DRAINS - 84"	87	LF				

