



ASC Region 7 Commercial Competition
Change Management: Owner Change Order Request

Description: **Cost for the buildout of the vivarium in the level 1 shell space.**

Reference: Initiating Document: Bulletin 16 CE # 1 PCCO # 1

Hensel Phelps Costs

1.	Labor	\$	<u>14,368</u>
2.	Material	\$	<u>39,249</u>
3.	Freight	\$	<u>2,500</u>
4.	Tax	\$	<u>3,434</u>
5.	Subtotal (Lines 1 - 4)	\$	<u>59,551</u>

Subcontractor Costs

6.	Plumbing	GIVEN	\$ <u>469,240</u>
7.	Mechanical	GIVEN	\$ <u>644,528</u>
8.	Electrical	GIVEN	\$ <u>528,050</u>
9.	Signage	GIVEN	\$ <u>4,347</u>
10.	Paint	GIVEN	\$ <u>27,894</u>
11.	Fire Protection	GIVEN	\$ <u>111,109</u>
12.	Ceilings	GIVEN	\$ <u>6,998</u>
13.	Cleaning	GIVEN	\$ <u>1,991</u>
14.	Framing		\$ <u>474,640</u>
15.	Epoxy Flooring		\$ <u>102,152</u>
16.	Subtotal (Lines 6 - 15)		\$ <u>2,370,950</u>

Total Costs

17.	Hensel Phelps & Subcontractor Direct Cost Total (Lines 5 & 16)		\$ <u>2,430,501</u>
18.	Hensel Phelps Bonds & Insurance	1.10%	\$ <u>26,736</u>
19.	Contractor Fee	6.00%	\$ <u>147,434</u>
20.	Total		\$ <u>2,604,671</u>

**HENSEL PHELPS**

Plan. Build. Manage.

ASC Region 7 Commercial Competition Change Management: Owner Change Order Request

Description: **Cost for the buildout of the vivarium in the level 1 shell space.**

Reference: Initiating Document: Bulletin 16 CE # 1 PCCO # 1

Subcontractor Costs

1.	Plumbing	GIVEN	\$ 469,240
2.	Mechanical	GIVEN	\$ 644,528
3.	Electrical	GIVEN	\$ 528,050
4.	Signage	GIVEN	\$ 4,347
5.	Paint	GIVEN	\$ 27,894
6.	Fire Protection	GIVEN	\$ 111,109
7.	Ceilings	GIVEN	\$ 6,998
8.	Cleaning	GIVEN	\$ 1,991
9.	Framing		\$ 474,640
10.	Specialties		\$ 62,197
11.	Epoxy Flooring		\$ 102,152
12.	Subtotal (Lines 1 - 11)		\$ 2,433,147

Total Costs

13.	Subcontractor Direct Cost Total		\$ 2,433,147
14.	Hensel Phelps Bonds & Insurance	1.10%	\$ 26,765
15.	Contractor Fee	6.00%	\$ 147,595
16.	Total		\$ 2,607,506



CE# 1
DATE: _____

Labor & Material Worksheet

		A	B	C	D (A * C)	G	H	I (A * G * H)	N (D+I)
Item #	Description	Quantity	Unit	Material		Craft Labor			TOTAL
				Cost/Unit	Cost	MH/Unit	Rate	Cost	
	Labor & Material								
1	SANIRAIL CRASH RAIL	605.00	LF	\$ 50.00	\$ 30,250.00	0.10	\$ 140.00	\$ 8,470.00	\$ 38,720.00
2	3 1/2" X 3 1/2" SS 4' CG	32.00	EA	\$ 175.00	\$ 5,600.00	0.10	\$ 70.00	\$ 224.00	\$ 5,824.00
3	10LB FIRE EXTINGUISHER	1.00	EA	\$ 356.00	\$ 356.00	0.05	\$ 70.00	\$ 4.00	\$ 360.00
4	ACROVYN 4000 - WP (4x10 SHEETS)	400.00	SF	\$ 7.00	\$ 2,800.00	0.10	\$ 140.00	\$ 5,600.00	\$ 8,400.00
5	FIRE EXTINGUISHER CABINET	1.00	EA	\$ 243.00	\$ 243.00	1.00	\$ 70.00	\$ 70.00	\$ 313.00
	Subtotal				\$ 39,249.00			\$ 14,368.00	\$ 53,617.00
								Freight	\$ 2,500.00
								Tax	\$ 3,434.29
								OH&P (6%)	\$ 3,217.02
								Total	\$ 62,768.31

Subcontractor Summary

Framing

Description: Install additional framing and drywall throughout the updated vivarium buildout in the shell space.

Reference: Initiating Document: Bulletin 16 CE # 1 PCCO # 1

Subcontractor Costs

1.	Labor & Material		\$	<u>399,263</u>
2.	Equipment		\$	<u>5,375</u>
3.	3rd Tier Sub Costs (Sub Name)		\$	<u>0</u>
4.	Subtotal (Lines 1 - 3)		\$	<u>404,638</u>
5.	Taxes	TAX INC.	\$	<u>0</u>
6.	Overhead & Profit	15%	\$	<u>60,696</u>
7.	Subtotal (Lines 4 - 6)		\$	<u>465,334</u>
8.	Bonds and Insurance	2%	\$	<u>9,307</u>
9.	Total		\$	<u>474,640</u>

Subcontractor Summary

Specialties

Description: Install handrails, wall protection, fire extinguishers, fire extinguisher cabinets, lockers, towel dispensers, and corner guards throughout the vivarium

Reference: Initiating Document: Bulletin 16 CE # 1 PCCO # 1

includes isec and I2

Subcontractor Costs

1.	Labor		\$ <u>10,257</u>
2.	Material		\$ <u>37,438</u>
3.	Equipment/Freight		\$ <u>2,305</u>
4.	3rd Tier Sub Costs (Sub Name)		\$ <u>0</u>
5.	Subtotal (Lines 1 - 4)		\$ <u>50,000</u>
6.	Taxes	8.75%	\$ <u>3,478</u>
7.	Overhead & Profit	15%	\$ <u>7,500</u>
8.	Subtotal (Lines 5 - 7)		\$ <u>60,978</u>
9.	Bonds and Insurance	2%	\$ <u>1,220</u>
10.	Total		\$ <u>62,197</u>

Subcontractor Summary

Epoxy Flooring

Description: Install epoxy flooring throughout the vivarium buildout

Reference: Initiating Document: Bulletin 16 CE # 1 PCCO # 1

Subcontractor Costs

1.	Labor		\$ <u>58,399</u>
2.	Material		\$ <u>26,659</u>
3.	Equipment		\$ <u>0</u>
4.	3rd Tier Sub Costs (Sub Name)		\$ <u>0</u>
5.	Subtotal (Lines 1 - 4)		\$ <u>85,058</u>
6.	Taxes	8.75%	\$ <u>2,333</u>
7.	Overhead & Profit	15%	\$ <u>12,759</u>
8.	Subtotal (Lines 5 - 7)		\$ <u>100,149</u>
9.	Bonds and Insurance	2%	\$ <u>2,003</u>
10.	Total		\$ <u><u>102,152</u></u>