



HENSEL PHELPS

Plan. Build. Manage.

Operations and Maintenance Facility East

Updated:

02/04/21

Estimate Summary

A	B	C	
DIV	Description	Design Development Budget 180,000 SF	
		\$/SF	Amount
DESIGN			
00	Site Survey, Geotechnical Report	4.17	\$ 750,000
00	Schematic Design Development	26.39	\$ 4,750,000
00	Design Development	26.32	\$ 4,738,000
00	Construction Documents	26.50	\$ 4,770,000
00	Construction Administration	6.94	\$ 1,250,000
	Subtotal - DESIGN	90.32	\$ 16,258,000
PRECONSTRUCTION SERVICES			
00	Schedule Development	0.51	\$ 91,200
00	Estimate Development	0.60	\$ 107,200
00	Pre-Con General Conditions	0.28	\$ 50,000
	Subtotal - PRE CON	1.38	\$ 248,400
GC			
01	General Conditions	79.88	\$ 14,379,148
	Subtotal - GC	79.88	\$ 14,379,148
BUILDING & SITE			
02	Selective Demolition	1.10	\$ 198,240
02	ATC - 1 (KING County Sewer Relocation)	0.89	\$ 160,000
02	ATC - 2 (King County Side Sewer)	(0.47)	\$ (85,000)
02	ATC - 3 (TOD Phase 2 Shear Wall)	(1.72)	\$ (310,000)
03	Concrete - MOW	1.82	\$ 328,280
03	Reinforcing - MOW	0.97	\$ 175,000
03	Concrete - OMF	9.72	\$ 1,750,000
03	Reinforcing - OMF	4.17	\$ 750,000
04	Concrete Masonry (CMU)	7.50	\$ 1,350,000
05	STRUCTURAL STEEL	29.93	\$ 5,387,520
05	Miscellaneous Metals & STAIRS	18.56	\$ 3,340,000
07	Roofing	4.19	\$ 755,000
07	EXTERIOR - METAL PANELS - MOW	11.67	\$ 2,101,430
07	EXTERIOR - METAL PANELS - OMF	21.40	\$ 3,852,000
08	Interior Glazing MOW & OMF	6.78	\$ 1,220,000
08	Doors, Frames, Hardware - MOW	0.42	\$ 75,316
08	Doors, Frames, Hardware - OMF	2.22	\$ 400,000
09	Drywall / Framing- MOW	2.73	\$ 492,122
09	Drywall / Framing - OMF	9.72	\$ 1,750,000
09	Tile	1.90	\$ 341,565
09	Acoustical Ceiling	5.56	\$ 1,000,000
09	Carpet, Resilient, RTF	5.79	\$ 1,042,528
09	Floor Leveling Allowance	0.42	\$ 75,000
09	Paint & Wall Covering	6.67	\$ 1,200,000
09	Final Cleaning	0.92	\$ 164,700

10	Signage - Interior	0.14	\$	25,000
10	Signage - Exterior	0.42	\$	75,000
10	Casework & Solid Surface Countertop	0.78	\$	140,000
10	Lockers (Metal & Plastic)	0.47	\$	85,000
10	Racking & Shelving	1.11	\$	200,000
10	Toilet and Bathroom Accessories	0.36	\$	65,000
10	Toilet Partitions	0.61	\$	110,000
11	Whiting - Car Host, Truck Hoist & Turntables	11.11	\$	2,000,000
11	Wheel Lathe Equipment	11.67	\$	2,100,000
11	Sanding Equipment	5.08	\$	915,000
11	Train Wash Equipment	6.86	\$	1,235,000
12	Window Shades	0.18	\$	32,000
14	Elevator	0.88	\$	158,000
21	Fire Protection	2.63	\$	474,000
22	Plumbing	47.22	\$	8,500,000
23	HVAC	92.08	\$	16,575,000
26	Electrical & Low Voltage Infrastructure	250.00	\$	45,000,000
26	Temp Lighting Allowance	0.56	\$	100,000
31	Site Work - Paving	8.33	\$	1,500,000
32	Site Modifications	0.83	\$	150,000
33	Site Utilities	5.56	\$	1,000,000
34	Track	266.67	\$	48,000,000
	Subtotal - BUILDING & SITE	866.40	\$	155,952,701
	PERMITS & FEES			
90	Plan Check and Permit Fees	4.72	\$	850,000
90	Encroachment Permit	2.34	\$	420,615
	Subtotal - PERMITS	7.06	\$	1,270,615
	CONTINGENCY / RESERVES	%		
90	Design	3.00%	\$	4,716,699
90	Buyout	4.00%	\$	6,288,933
90	Construction	4.00%	\$	6,288,933
	Subtotal - CONTINGENCY	96.08	\$	17,294,565
	INSURANCE & BONDS	%		
90	Builder's Risk	0.50%	\$	872,589
90	GL Insurance	0.53%	\$	924,945
90	Bond	0.62%	\$	1,082,011
	Subtotal - BOND & INSURANCE	16.00	\$	2,879,545
	FEES	%		
90	Contractor's Fee	5.00%	\$	10,414,149
	Subtotal - FEES	57.86	\$	10,414,149
	TOTAL CONSTRUCTION COST	1,214.98	\$	218,697,122