

## SUSTAINABILITY PART C ANSWER SHEET

1. What is the Minimum Efficiency Reporting Value (MERV) for the filtration media that shall be installed at the air handling units prior to the flush-out? 13
  - a. Specification Subsection Reference: 01 81 19-2.1-B
2. How many cubic feet of outside air per square foot of floor area need to be provided to complete the flush-out? 14,000
3. Given the ventilation rate provided by the mechanical contractor, how many days will the flush-out take to complete for the City Hall building, assuming the HVAC system is running 24/7? (Round to the nearest whole day)  
14 Days