

Godzilla Builders Inc.



QUOTE

4321 Kong Avenue, Bakersfield, CA 93305
(661) 909-7890 | (661) 909-7891
godzillabuildersinc.com

QUOTE #: 1000-695
Date: 2/9/23

To:
All Bidders

Expiration Date: 3/9/23

Qty	Description	S/T Labor Rate	O/T Labor Rate	D/T Labor Rate
	Carpenter	\$107.52	\$148.59	\$189.62
	Cement Mason	\$103.41	\$142.97	\$181.54
	Laborer - General	\$98.80	\$132.78	\$168.59
	Laborer – Pipelayer	\$101.76	\$138.96	\$172.16
	Laborer Foreman	\$110.37	\$153.28	\$179.58
	Operator	\$118.45	\$163.87	\$199.85
	Operator Foreman	\$123.85	\$170.22	\$207.63
	Pipefitter Foreman	\$123.85	\$170.22	\$207.63
	Pipelayer	\$118.45	\$163.87	\$199.85
	Sandblaster	\$98.80	\$132.78	\$168.59
	Welder	\$121.57	\$168.25	\$203.64
	Welder Helper	\$86.96	\$121.35	\$153.87
	<u>Equipment Rates</u>	<u>Hourly Rate</u>	<u>Min. Hours</u>	
	1 TON Flatbed Truck	\$23.30	4	
	Sandblast Pot	\$44.90	4	
	Welding Rig (Minimum Hours = 4)	\$36.40	4	

General Terms & Conditions:

1. All labor can be dispatched individually. Craft employee will become part of Contractor's crew and work will be performed under the direct supervision and control of the customer (even with foremen).
2. All equipment can be dispatched individually.
3. Welding needs will require a Welder, Welder Helper, 1 TN Flatbed Pickup, and Welding Rig to be dispatched together.
4. S/T (standard) hourly rates exclude Saturday, Sunday, or weekend work. S/T rates apply for weekday work up to 8 hours; lunch required. Saturday work requires O/T (overtime) rates up to 8 hours, then D/T (double-time) rates will be in affect. D/T rates apply for Sunday and holiday work.
5. All union regulations apply.



BAKERSFIELD OFFICE:
2800 Downey Ct.
Bakersfield, CA 93309
Phone: 661-898-9687
License No. 3019687
DIR No. 10000098674

PROPOSAL / CONTRACT

Date: 2/9/2023

To: GENERAL CONTRACTORS

Subject Job: KERN TULARE WATER DISTRICT
GUZMAN WATER RESERVOIR

We propose to furnish at the above job all labor, materials, equipment, supervision, Workers' Compensation Property Damage and Liability Insurance necessary to complete in a thoroughly workmanlike manner all the work described below.

REVISED PRICING

PROVIDE PAINTING PER PLANS AND SPECIFICATIONS OF ITEMS AS LISTED:

- TRASH RACK
- VALVE LIFT PEDESTAL
- LOW LEVEL VALVE ASSEMBLY (NOT BURIED)
- LADDER & RAILING AT PLATFORM

TOTAL AMOUNT: \$12,500.00

EXCLUSIONS:

1. BELOW GRADE PIPE, INTERIOR OR PIPE
2. ISOLATION COATING OF DISSIMILAR SURFACES AND EMBEDDED ITEMS
3. FUSION BONDED EPOXY COATING
4. EXTERIOR PRIMING OF STRUCTURAL STEEL
5. ANY OTHER ITEMS NOT MENTIONED ABOVE

NOTE:

1. TRASH RACK AND PLATFORM OUTLET VALVE TO BE FINISH PAINTED PRIOR TO INSTALATION.
2. CONTRACTOR TO PLACE ITMES ON WOOD DUNNAGE APPROXIMATELY 1" OFF OF GROUND PRIOR TO COATING.
3. SHOULD THIS CONTRACT BE AWARDED, THIS DOCUMENT IS TO BECOME PART AND PARCEL TO THE CONTRACT.

ADDENDUMS 1-2 NOTED

NOTE: THIS PROPOSAL SPECIFICALLY EXCLUDES REPAINTING OF DAMAGES CAUSED BY OTHERS AND ACCEPTANCE OF SURFACES TO BE PAINTED. ALL REPAIRS OF DAMAGES WILL BE PERFORMED PER PDCA DOCUMENT P1-92 "TOUCH-UP PAINTING AND DAMAGE REPAIR FINANCIAL RESPONSIBILITY", LOS ANGELES COUNTY PDCA "POSITION PAPER ON PAINTER TOUCH-UP" AND PDCA P4-94 "RESPONSIBILITY FOR INSPECTION AND ACCEPTANCE OF SURFACES PRIOR TO PAINTING AND DECORATING. TOUCH-UP IS DEFINED AS: The correction of deficiencies in the specified work to achieve a properly painted surface. The correction of damages by others is separate from touch-up and will be considered extra work and will be completed upon acceptance of a proposal or a work directive to proceed with repairs of damages for additional cost.

STATE LICENSE NO. 768110
DIR REGISTRATION NO. 1000008968

The Painting Co. : _____
Chris Adler, Estimator

TERMS: This proposal must be accepted within 30 days of the date hereof to become a valid contract.

ACCEPTANCE - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined.

If approved and accepted, please sign below and return a copy to our office.

Date of Acceptance: _____

Signature: _____



QUOTE

Expiration Date: 3/9/2023

Salesperson	Job	Payment terms	Due date
Hank Gutierrez	Sales rep	Due on receipt	TBD

Qty	Description	Unit price	Line total
	Hydroseeding	\$0.08 / SF	
	Fiber Rolls	\$3.50 / LF	
Subtotal			-
Sales Tax			N/A
Total			-

1. Overtime, weekend, holiday, or night work.
2. Contractor to provide water source onsite.
3. Quote only includes labor and equipment to install quoted items, material not included.
4. Soil Preparation, placement of topsoil, duff, or incorporation.
5. Weed removal or plant establishment.
6. Maintenance and reseeding.
7. Removal of temporary items.

Thank you for your business!



685 Union Ave. Bakersfield, CA 93305
Phone: 661-528-8875
FAX: 661-528-9000
DIR No. 1000003362

Cost Estimate
QC Services for Soil Testing &
Compaction / Concrete

Contract Name: Guzman Reservoir

Bid Date: February 9, 2023

Quote No.: 10008967

Description	Quantity	Unit	Rate	Amount
QC Plan and Support				
Development of Quality Control Plan	1	Each	\$ 1000	\$ 1000
Field QC Services - Soil & Compaction / Concrete				
1 QC Manager / Tester / Sampler (Monday-Friday) - Soil Technician Performing Field QC (Lab Testing included in shift rate)		Shift	\$ 2,150	\$ TBD
Concrete Technician (Tester / Sampler, M-F)-Lab Testing included in shift rate		Shift	\$ 2,150	\$ TBD
Additional Laboratory Testing Services				
Sand Cone		Test	\$ 200	\$ TBD
Plasticity Index		Test	\$ 250	\$ TBD
Aggregate Gradation		Test	\$ 200	\$ TBD
Field Total				\$

Remarks:

- 1 Estimate is based on 8 hour shifts, Monday through Friday and Saturday.
- 2 Overtime will be charged at \$200/hour. Double time will be charged at \$250/hour.
- 3 Tester is from Kern County so no daily subsistence required.
- 4 Union Tester rates quoted are valid through December 31, 2023, after which an annual escalation rate of \$24/shift for each Tester will be added onto the shift rate.



Address: 1100 Candlestick Ave. Tulare CA 93274
Office #559-701-2854 Fax #559-701-2800
CA Contractors Licence # 1193685
marty.hamm@reynoldstruckinginc.com

2-9-2023

To: All Bidders

Subject: Trucking Proposal for the Guzman Reservoir material import

Thank you for considering Reynolds Trucking, Inc. for your project. Reynolds will provide trucks to import materials from the listed sources delivered to the Guzman Reservoir for the following per ton prices.

Material Type	Source	Price
Rip Rap	API Fountain Springs	\$ 8.66 per ton
Drainage layer	API Main Plant	\$ 11.35 per ton
Bedding Sand	API Main Plant	\$ 11.35 per ton
Sand Blanket	API Clinton Sand Pit	\$ 200.00 per load

API stands for Aggregate Planning Inc. If material comes from another source, use the hourly rate charge as listed below per truck type. Assume Bottom, Side, and End Dumps hold 25 TN, Transfers hold 24 TN, and Super 10s hold 16 TN. We will charge a 6 hour minimum for hourly rates. Prices below are for daytime work, if night time work add 20%.

Hourly price as follows:

Bottom Dump	\$ 140.00
Side Dump/End Dump	\$ 150.00
Transfer	\$ 155.00
Super 10	\$ 135.00

Respectfully,

Marty Hamm



Quote #: AQ100068745

Project: **Guzman Reservoir**

Bid Date: 2/9/2023 **Bid Time:** 9:30PM

Estimator: Ralph Clark **Addendums:** All

Municipality: Kern Tulare Water Dist.

Project Location: Kern County, CA, USA

Engineer:

Job Notes:

Please review the last page for Additional Notes

STATE AND LOCAL SALES TAXES ARE NOT INCLUDED IN THE PRICE OF OUR QUOTATION

BUY AMERICA AND EPA AMERICA IRON & STEEL REQUIREMENTS

Take off notes and Exclusions:

The Fabricated steel items must be submitted for final approval before placing order. The lengths, end types and degree of fittings not called out are subject to the estimators interpretation of the plan.

The material and quantities shown are for bidding AND Budget purposes ONLY.

The Materials, including Material Specifications and quantities necessary for construction are the CONTRACTOR's responsibility to verify. Please contact the estimator for clarification or questions.

Our quantities, based on the interpretation of the plans, may vary from yours, if so use per each, per ton, per foot pricing to adjust quantities up or down.

Excluded: Any items not listed in this quote are to be considered excluded OR by others including fabricated plates and coatings including epoxy and cement lined items after assembly or welded materials.

•• Items noted as no quote are excluded in this quote ••

seepage outlet drain
low level outlet structure

Description / Comments	UM	Qty	Final Bid Price	Extended Bid Price
54" Steel Plate- Seepage Drain	EA	1	\$800.00	\$800.00

low level outlet structure: **\$800.00**
seepage outlet drain: **\$800.00**

low level valves
low level INTAKE

Description / Comments	UM	Qty	Final Bid Price	Extended Bid Price
24" SLIDE GATE WITH STEM GUIDES see page 6 for additional hardware included	EA	1	\$34,728.24	\$34,728.24

low level INTAKE: **\$34,728.24**
low level valves: **\$34,728.24**

low level valves
low level outlet structure

Description / Comments	UM	Qty	Final Bid Price	Extended Bid Price
12" 125lb STEEL FLANGED GATE VALVE	EA	1	\$4,875.00	\$4,875.00

low level outlet structure: **\$4,875.00**
low level valves: **\$4,875.00**

low level Outlet

Description / Comments	UM	Qty	Final Bid Price	Extended Bid Price
LLOS Misc Metals inc. 1 EA 4'6"x6'4" Channel Supp. Frame Struct. Galv. 1 EA 2'6"x4'6" x 1-1/4" Serrated Grate Galv, 12'6" LF - Two Line Steel Angle Handrail Galv, 1 EA 8'6" Long Galv Steel Ladder	EA	1	\$18,895.00	\$18,895.00

low level Outlet: **\$18,895.00**
low level Outlet: **\$18,895.00**

low level Outlet
Trash Rack Assembly

Description / Comments	UM	Qty	Final Bid Price	Extended Bid Price
Trash Rack Assembly Consist. of 1 EA 4'6"x6'0-3/4" Long Upper Trash Rack w/ ASTM A36 Steel Flatbar, Angle & Plate w/ attachment bolts and nuts all Galv, 1 EA 4'6"x2'6-3/4" Long Lower Trash Rack w/ ASTM A36 Steel Flatbar, Angle & Plate w/ attachment bolts & nuts, all Galv	EA	1	\$24,995.00	\$24,995.00

low level Outlet: **\$24,995.00**
low level Outlet: **\$24,995.00**

ADDITIONAL NOTES:

TAKE OFF NOTES & EXCLUSIONS: SOME OF THE STEEL PIPE FITTINGS ARE BARE AND DO NOT INCLUDE SPECIFIED FINISH COATINGS.

STEEL FABRICATION FOR THIS PROJECT ARE NON-STOCK, NON-CANCELLABLE AND NON-RETURNABLE

Notable items excluded: Trash Rack, epoxy in field applications, water stops for structures, valve platform grating, various mounting plates and boltup hardware, rebar, ladder, vent pipe supports. 1/2" steel plate for 54" drainage structure, Rodent screens on vent pipes and ends of pvc pipe.

Slide Valve includes the following:

24 Inch Diameter Pressure Slide Gate (Model P-30-FF)

Frame FF Ext Flangeback Cast Iron: ASTM A-126 CL B

Cover Cast Iron: ASTM A-126 CL B

Gate Designed for 60 Ft Seating and 10 Ft Unseating Head

Lift & Stem based on Operating heads 40 ft. Seating and 0 ft. Unseating

Gate Invert to Top of Wall 137.46 ft.

Stem Stainless Steel Type 304

K-2 Stem Guides; 2.5" Vent Pipe

Geared Lift

Mounting hardware Stainless Steel Type 304

Submittal Drawings includes the complete assembly (stem extension, all the guides, couplings, lift mounting bracket, etc). The contractor will need to provide epoxy for the anchor bolts.

Price of quoted material includes delivery to jobsite.

Quoted prices are based upon receipt of the total quantity for immediate shipment (48 hours). SHIPMENTS BEYOND 48 HOURS SHALL BE AT THE PRICE IN EFFECT AT TIME OF SHIPMENT UNLESS NOTED OTHERWISE. Quotes for products shipped for resale are not firm unless otherwise noted. Seller not responsible for delays, lack of product or increase of pricing due to causes beyond our control, and/or based upon Local, State and Federal laws governing type of products that can be sold or put into commerce. This Quote is offered contingent upon the Buyer's acceptance of Seller's terms and conditions.



Magic Mud Ready Mix Concrete Supply

1000 Glendale Ave
Bakersfield, CA 93308
Phone: 661-352-9999
Fax: 661-352-9000

February 9, 2023

To: All Bidders
ATTN: Estimator

Project: Kern-Tulare Water District Guzman Reservoir Project
Quote valid until December 31st 2023

Thank you for allowing MMRMCS the opportunity to give pricing on the above-mentioned project. The products and pricing have been formulated from information that has been provided by you and your company. Should there be any changes in the original information, MMRMCS pricing would become invalid and the project would need to be re-quoted.

Concrete:

Assume 10 CY per Full Load

4000 PSI 1" Concrete Mix; Mix ID: 600CWR
\$110.00 per cubic yard delivered

3000 PSI 3/4" Concrete Mix ; Mix ID: 550CWR
\$105.00 per cubic yard delivered

100 PSI Backfill Concrete Low Strength Mix ; Mix ID: 319CLSM
\$90.00 per cubic yard delivered

MMRMCS Concrete currently has a mix design in place for all 3 of these designs.

Additional Charges:

1. AB 219, Public Works Delivery Charge = \$260.00 per Load (Required on all Public Works Jobs)
2. Environmental Surcharge: \$30.00 per Load (Required on all Loads)
3. Low Carb Surcharge: \$6.50 per Load (Required on all Loads)
4. Return Concrete Surcharge: \$150.00 per Load (if applicable)

Additional Add-Ons:

Saturday Delivery Short Load (4 cy or less)	\$5.00 per yard in addition to quoted price
Plasticizer	\$50.00 per load
UltraFiber 500	\$8.00 per gallon
Chilled Water	\$5.00 per yard for 1.5lbs per yard
Heated Water	\$1.50 per yard
Non-Chloride Accelerator	\$1.50 per yard
Integral Color	\$5.80 per 1% - per cubic yard
Stand By Time	Please Call
truck arrives on jobsite	\$1.50 per minute once 6 min. per yard free time expires when

General Conditions:

- ☐ **Concrete subject to availability. At this time, we require 1-2 weeks notice prior to delivery.**
- ☐ **Approved submittal required prior to any concrete delivery Price subject to change if specifications become available or specifications change**
- ☐ **Buyer to provide safe access to job site and haul roads.**

All pricing is for deliveries within the immediate Kern County area during our normal business hours. Should there be a need for off-hour; weekend or holiday deliveries please contact us immediately for additional pricing and coordination.

All above mentioned products are subject to California State Sales tax applicable to delivery location.

Thank you for considering Magic Mud Ready Mix Concrete Supply any of your concrete needs. We look forward to servicing your projects.

Sincerely,

Kevin Doogan
Sales Manager



Quotation

Quote Date: 2/9/23

Bid Date: 2/9/23

Project: Guzman Water Reservoir

Agency: Kern-Tulare Water District

Project No.: 17897

Qualification Statement

- Quote is based on the following plans, specification, and addendums: **Drawings dated 06/19/19 & Kern-Tulare Water District Specs**
- Domestic Material: ☒ This quote meets domestic material requirements as set forth in the project specifications
☐ This quote is not intended to meet any type of domestic material requirements
- All material used will conform to current AWWA standards.

Pricing Table					
Item	Qty.	Unit	Description	Unit Price +Tax	Total +Tax
12	1	LS	LOW LEVEL OUTLET PIPING – 30" INTAKE STRUCTURE TO 12" GATE VALVE Includes Low Level Outlet Piping as shown from Sta. 0+45.75 to Intake at Sta. 0+3+88.00 +/- Includes all bend, reducers, tees, and 2.5" flanged vent outlet (vent by others)		\$85,200.00
Total (tax not included)					\$85,200.00

Project Terms & Conditions:

- Prices quoted are firm for orders placed by (30 days from quote).
- Tax not included in quoted price above.
- Any revisions to the scope of work may necessitate a price revision and an approved change order prior to the revision being effective.
- Shop drawings can be submitted approx 2 weeks after receipt of order. Delivery can begin 12-16 weeks after receipt of approved shop drawings.
- FOB: Prices are F.O.B. Destination
- Shipping rate and firm delivery will be arranged by mutual agreement between Seller and Buyer upon receipt of approved drawings. .
- The Buyer will give (48) forty-eight hours notice to Seller for scheduling delivery of pipe and materials.
- Bracing & Shipping Cradles: All pipe as required, will be braced with stulls on each end. This bracing is for shipping purposes only and not designed for grouting or installation loads. Any special requirements, i.e. vertical elongation etc., will be the sole responsibility of the Buyer. Shipping cradles and stulls are property of Seller and are to be grouped and reloaded on trucks, at the Buyers expense, for reuse by Seller, if requested. Please note that any bunks or stulls not returned in reusable condition will be billed to the Buyers account at full replacement cost.
- Schedule: Any revised delivery schedule will be negotiated between Buyer and Seller and will take into account Sellers current schedules of work.
- Price excludes off-loading of pipe, installation, field welding of pipe sections, or supervision.
- Price excludes valves, nut-bolt-gasket kits, meters, hydrant heads, piping other than steel listed above, expansion joints, ductile iron pipe, PVC pipe, any type of cathodic protection, and any type of pipe hangers or supports, and any type paint for field application/repair.
- Seller will not recognize back-charges of any kind that are caused by trucking delays, Seller supplier delays, weather, or items beyond Seller's control. Seller must be notified of all problems to participate in and/or approve any corrective action. Any claim must be received by the Seller in writing, within 7 calendar days from date of occurrence. Seller will not be held liable for liquidated damages of any kind.

Thank you for the opportunity to quote this project. Should you have any questions or concerns please feel free to reach out.

Sincerely,
North Shore Pipe