

INTEGRATED FABRICATION

Date: May 30, 2023

Attn: Bianca Guzman

Subject: Carpenter creek Culvert

Scope of Work:

INTEGRATED FABRICATION is pleased to provide the following Fixed Price bid as described below. We would be happy to meet with you to further refine this estimate, if needed. We have based our estimate on the drawing Bianca Guzman with Granite Construction sent to us.

I.F. proposes to do the following:

- **Weld 108 connection points varying between 5"x5 1/2"x 1/4" plates, 3"x 5"x 1/4" plates, and 5" long 2"x 2" x 1/4" angle with 1/4" single pass file welds.**

Schedule:

I.F. will complete the welds in two phases first being approximately 64 welds, the second being approximately 44 welds in two ten hour shifts using four welders.

Price:

all 108 Weld plates would be completed in a total of 80 man hours using core shield 8 welding wire. would complete the project operating on 1 shift with 4 welders in two phases. will also provide 1 project manager for 4 hours and 1 CWI 20 hours for visual inspections and 4 hours reporting time. For a fixed price of **\$25,176.00**

Invoicing:

terms for this project are NET 30 and an invoice will be submitted to you at the end of each month or at the end of the project, whichever comes first.

Assumptions:

- This quote is valid for 30 days.
- **I.F.** HAS unobstructed access during the 10-hour workday.
- **I.F.** TO provide no materials.
- **I.F.** TO Provide CWI for Visual Inspections only
- **I.F.** TO provide 1 project manager for 4 hours for weld inspections.

Exclusions:

- Sales Tax
- All Permitting and inspection other than visual weld inspection.
- Engineering or Detailing
- Fire watches
- Paint and Coatings
- Weld plates and other materials

We appreciate feedback and the opportunity.

ACCEPTANCE AND AUTHORIZATION TO PROCEED:

_____ **Date** _____

PRINTED NAME

ATTACHMENT: STANDARD TERMS AND CONDITIONS (JAN 2021)