

Jenny Pipe LLC

Bill to:	PLAN HOLDERS QUOTATION	Project:	TIGER FIRST/LAST MILE PROGRAM - LEHI CITY P
			LEHI, UT
Contact:		Project Manager:	
Phone :	Fax:	Phone :	Fax:
Customer ID:	PO:	ShipVia:	Sales Rep:
Terms:	NET 30 Days	Bid Date:	

Qty	Item	Description	Unit Price	TX	Extension
Structure: <input type="checkbox"/> NOTES Station:					
1	QN	QUOTE NOTES	\$0.00	<input checked="" type="checkbox"/>	\$0.00
		DUE TO OUR CURRENT BACKLOG, LEAD TIMES FOR NEW ORDERS IS APPROX. 9-11 WEEKS AFTER SUBMITTALS ARE APPROVED. THIS LEAD TIME WILL CHANGE AS THE YEAR PROGRESSES. WE ENCOURAGE YOU TO GET AN UPDATED LEAD TIME UPON AWARD OF PROJECT			
					\$0.00

Structure: <input type="checkbox"/> MH4-07 Station: STORM 4' DIA. MH STORM W/ FLAT FLOOR					
1	CIR1180	A-1180 RING NO NOTCH	\$156.00	<input checked="" type="checkbox"/>	\$156.00
1	MHEL48	48 IN ECCENTRIC CONCRETE LID	\$290.26	<input checked="" type="checkbox"/>	\$290.26
1	MHS48X1	48 IN X 1 FT MH SECTION	\$189.32	<input checked="" type="checkbox"/>	\$189.32
1	MHBFF48X6M	48 IN X 6 FT PRECAST FF BASE (MONO)	\$896.78	<input checked="" type="checkbox"/>	\$896.78
1	CICSD	COVER - STORM DRAIN	\$153.20	<input checked="" type="checkbox"/>	\$153.20
2	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$30.74
6	RS12	RUBBER STEP - 12"	\$7.78	<input checked="" type="checkbox"/>	\$46.68
					\$1,762.98

Structure: <input type="checkbox"/> CB2-07 Station: CUSTOM BOX VAULT					
1	CIFGGF1BS	UDOT GF1 BIKE SAFE FRAME & GRATE	\$693.00	<input checked="" type="checkbox"/>	\$693.00
1	SPBL	CUSTOM BOX LID 9.00' X 4.00' X 0.666666666666667' x 0.666666666666667	\$930.00	<input checked="" type="checkbox"/>	\$930.00
1	SPBB	CUSTOM BOX BASE 8' X 3' X 5.98'	\$2,591.00	<input checked="" type="checkbox"/>	\$2,591.00
7	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$76.23
3	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$46.11
					\$4,336.34

Structure: <input type="checkbox"/> PIPE Station: PIPE PIPE					
80	RCPS312	12 IN DIA RCP CL III - AIRTESTED	\$13.74	<input checked="" type="checkbox"/>	\$1,099.20
3	RCPEB12	12 IN CONC END SECT - BELL	\$331.35	<input checked="" type="checkbox"/>	\$994.05
192	RCPS315	15 IN DIA RCP CL III - AIRTESTED	\$15.12	<input checked="" type="checkbox"/>	\$2,903.04
2	RCPEB15	15 IN CONC END SECT - BELL	\$354.78	<input checked="" type="checkbox"/>	\$709.56
152	RCPS318	18 IN DIA RCP CL III - AIRTESTED	\$17.81	<input checked="" type="checkbox"/>	\$2,707.12
320	RCPS518	18 IN DIA RCP CL V - AIRTESTED	\$25.03	<input checked="" type="checkbox"/>	\$8,009.60
1	RCPEB18	18 IN CONC END SECT - BELL	\$380.25	<input checked="" type="checkbox"/>	\$380.25
248	RCPS324	24 IN DIA RCP CL III - AIRTESTED	\$23.43	<input checked="" type="checkbox"/>	\$5,810.64
1	RCPEB24	24 IN CONC END SECT - BELL	\$437.83	<input checked="" type="checkbox"/>	\$437.83

Qty	Item	Description	Unit Price	TX	Extension
Structure: <input type="checkbox"/> PIPE		Station: PIPE PIPE			
					\$23,051.29
Structure: <input type="checkbox"/> CB2-08		Station: UDOT UDOT CB5A 4X4 CATCH BASIN			
1	CIFGGF1	9221 F&G STANDARD UDOT GF1 GALV	\$590.00	<input checked="" type="checkbox"/>	\$590.00
1	UDOTL5A4X4H19	UDOT CB5A Lid (4X4) w/ 19"X44" Opening	\$515.00	<input checked="" type="checkbox"/>	\$515.00
1	UDOTB5A4X4	UDOT CB-5A BASE 4' X 4' x 4.14'	\$1,275.00	<input checked="" type="checkbox"/>	\$1,275.00
2	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$30.74
5	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$54.45
					\$2,465.19
Structure: <input type="checkbox"/> CB4-01		Station: UDOT UDOT CB5A 4X4 CATCH BASIN			
1	CIFGGF1	9221 F&G STANDARD UDOT GF1 GALV	\$590.00	<input checked="" type="checkbox"/>	\$590.00
1	UDOTL5A4X4H19	UDOT CB5A Lid (4X4) w/ 19"X44" Opening	\$515.00	<input checked="" type="checkbox"/>	\$515.00
1	UDOTR5A4X4	UDOT CB-5A RISER 4' X 4' x 2.31'	\$623.68	<input checked="" type="checkbox"/>	\$623.68
1	UDOTB5A4X4	UDOT CB-5A BASE 4' X 4' x 4.5'	\$1,275.00	<input checked="" type="checkbox"/>	\$1,275.00
4	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$61.48
8	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$87.12
					\$3,152.28
Structure: <input type="checkbox"/> CB4-02		Station: UDOT UDOT CB5A 4X4 CATCH BASIN			
1	CIFGGF1	9221 F&G STANDARD UDOT GF1 GALV	\$590.00	<input checked="" type="checkbox"/>	\$590.00
1	UDOTL5A4X4H19	UDOT CB5A Lid (4X4) w/ 19"X44" Opening	\$515.00	<input checked="" type="checkbox"/>	\$515.00
1	UDOTB5A4X4	UDOT CB-5A BASE 4' X 4' x 3.02'	\$1,275.00	<input checked="" type="checkbox"/>	\$1,275.00
2	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$30.74
4	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$43.56
					\$2,454.30
Structure: <input type="checkbox"/> CB4-06		Station: UDOT UDOT CB5A 4X4 CATCH BASIN			
1	CIFGGF1BS	UDOT GF1 BIKE SAFE FRAME & GRATE	\$693.00	<input checked="" type="checkbox"/>	\$693.00
1	UDOTL5A4X4H19	UDOT CB5A Lid (4X4) w/ 19"X44" Opening	\$515.00	<input checked="" type="checkbox"/>	\$515.00
1	UDOTB5A4X4	UDOT CB-5A BASE 4' X 4' x 4.27'	\$1,275.00	<input checked="" type="checkbox"/>	\$1,275.00
2	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$30.74
5	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$54.45
					\$2,568.19
Structure: <input type="checkbox"/> OS3-03		Station: UDOT UDOT CB5A 4X4 CATCH BASIN			
1	CIFGGF1	9221 F&G STANDARD UDOT GF1 GALV	\$590.00	<input checked="" type="checkbox"/>	\$590.00
1	UDOTL5A4X4H19	UDOT CB5A Lid (4X4) w/ 19"X44" Opening	\$515.00	<input checked="" type="checkbox"/>	\$515.00
1	UDOTB5A4X4	UDOT CB-5A BASE 4' X 4' x 5.09'	\$1,345.00	<input checked="" type="checkbox"/>	\$1,345.00
2	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$30.74
6	RS14	14" RUBBER STEP	\$10.89	<input checked="" type="checkbox"/>	\$65.34
					\$2,546.08
Structure: <input type="checkbox"/> CB2-04		Station: UDOT UDOT DB1 2X2 CATCH BASIN			
1	CIFGDB1A	DB-1A 2X2 GALV FRAME & GRATE (UDOT)	\$485.00	<input checked="" type="checkbox"/>	\$485.00
1	UDOTBDB12X2	UDOT DB-1 BASE 2'X2' x 3.55'	\$705.00	<input checked="" type="checkbox"/>	\$705.00

Qty	Item	Description	Unit Price	TX	Extension
Structure: <input type="checkbox"/> CB2-04 Station: UDOT UDOT DB1 2X2 CATCH BASIN					
					\$1,190.00
Structure: <input type="checkbox"/> CB2-03 Station: UDOT UDOT DB1 30"X30" CATCH BASIN					
1	CIFGDB1A-2.5X2.5	DB-1A 30"X30" GALV FRAME & GRATE (UDOT)	\$623.80	<input checked="" type="checkbox"/>	\$623.80
1	UDOTBDB12.5X2.	UDOT DB-1 BASE 30"X30" x 4.62'	\$815.00	<input checked="" type="checkbox"/>	\$815.00
BOX WILL HAVE EPOSED REBAR IN TOP - FOR APPROACH SLAB TO BE CONNECTED TO					\$1,438.80
Structure: <input type="checkbox"/> CB3-01 Station: UDOT UDOT DB1 30"X30" CATCH BASIN					
1	CIFGDB1A-2.5X2.5	DB-1A 30"X30" GALV FRAME & GRATE (UDOT)	\$623.80	<input checked="" type="checkbox"/>	\$623.80
1	UDOTBDB12.5X2.	UDOT DB-1 BASE 30"X30" x 4.5'	\$835.00	<input checked="" type="checkbox"/>	\$835.00
1	SPBR	UDOT DB-1 RISER 30"X30" x 2'	\$675.00	<input checked="" type="checkbox"/>	\$675.00
3	MASJT1.25	1 1/8in X 3/4in X 14 FT JOINT MASTIC	\$15.37	<input checked="" type="checkbox"/>	\$46.11
BOX WILL HAVE EPOSED REBAR IN TOP - FOR APPROACH SLAB TO BE CONNECTED TO					\$2,179.91

Total Weight 298,632

Taxable	\$47,145.36
Non-Taxable	\$0.00
Sub Total	\$47,145.36
Tax	\$3,653.70
Total	\$50,799.06

Prices quoted are firm for thirty days from bid date.

All prices are quoted F.O.B. Jobsite. Material will be delivered only to locations that can be readily accessed by a loaded truck and trailer under its own power. Customer is to furnish labor and equipment to unload materials, unless seller notes otherwise. Should the truck remain on the jobsite for more than one hour the customer will be liable for a \$120 charge billed in ten minute increments.

Prices quoted are based on full truckload quantities. Products that must be delivered in less-than-truckload lots will be subject to an additional charge depending on the size of the lot and distance of the delivery.

Items and quantities shown have been established by seller review of plans and specifications. All items and quantities are shown for buyers convenience only and the seller shall not be liable for any take-off errors or extension errors. If the seller has been given an incorrect number of units, it is agreed that the buyer shall pay the per unit price for the number of units actually delivered.

Any special products ordered and/or produced, may be invoiced to the customer when ready for shipment.

Undamaged, standard products that are returned will be subject to a restocking fee of 20% of the invoice price. Freight costs for trucks to return products will be charged. Special order and custom produced products cannot be returned and are not eligible for a credit.

In the event of significant delay or price increase of material occurring during the performance of the contract through no fault of the Contractor, the contract sum, time of performance, and contract requirements shall be equitably adjusted by change order in accordance with the procedures of the contract documents. A change in price of an item of material shall be considered significant when the price of an item increases (An agreed upon percentage) percent between the contractual date and the date of installation.

AFTER JOB IS AWARDED, A JOB INFORMATION SHEET IS REQUIRED BEFORE SHIPPING OF ANY PRODUCT.

SUBMITTAL APPROVALS ARE REQUIRED BEFORE PRODUCTION CAN BE SCHEDULED FOR CUSTOM PRODUCTS AND PROCUREMENT OF STOCK ITEMS. SUBMITTAL APPROVAL MAY REQUIRE CHANGES TO QUOTED PRODUCTS AND RESULT IN ADDITIONAL COSTS - TO BE COVERED BY THE CONTRACTOR