

Project: Lehi Ped bridge overpass

We Propose To Furnish the Following Material:

RENTAL:

- Bent #2,3, or 4 **Shoring** utilizing Waco Hi-load Vertical frames, Aluma beam stringer, aluma beam joists & guardrail stanchions (up to 18' shoring height, 14'x31' platform, enough shoring for 1 cap.) **\$575/ 30 days**
- Bent #2, 3, or 4 **forming** utilizing Alisply straight gang forming system including: panels, connecting clamps, scaffold brackets and she bolts (this is enough for 1 complete abutment 5'-2" tall, 23' long x 5'-6" wide, customer is responsible for thru rod.) **\$625/ 30 days**
- Bent #1, or 5 **forming** utilizing Alisply straight gang forming system including: panels, connecting clamps, scaffold brackets and she bolts (this is enough for 1 complete abutment, w/ taper ties, customer is responsible for thru rod.) **\$1,200/ 30 days**
- 4'x4' x 18' tall square columns utilizing Alisply gang forms **\$625/ ea/ 30 day**
- 60" x 18' Steel Circular Column Form (including walkways, ladders connecting hardware, & Tilt up braces, 8'+8'+2' columns. **\$850/ 30 days**
- If forms are returned dirty and unoiled (make sure there is no slurry on the forms) **2% of form value**
 - count forms on arrival to verify yard count and notify For Shor of discrepancies ASAP if any.
 - count forms on departure and send with truck so For Shor can compare their count against yours and contact you if any discrepancy.
 - if Self Consolidating Concrete is used contractor must inform For-Shor before any drawings are started.

Note : Contractor supplies 3/4" plywood and any miscellaneous wood required For forming and shoring. It is the contractor's responsibility for an engineering stamp if necessary.

- C49 Bridge overhang bracket (with guard rail pocket, 54", approx 220 req'd) **\$4.75/ ea/ 30 days**

PURCHASE:

- P.E. stamp (if required, if a site walk is required it would be an additional cost) **\$600**
- Delivery (from when it leaves until it gets back) **\$95/ hr**
- #1203 Random Ashlar stone formliner (based on (24)- 4'x 10' , single use, FOB Factory) **\$98/ sheet**
- HF33 (std), 90°/90° hanger, 49" long (plated, FOB TX, 4 week notice) **\$10.29/ea**
- HF34 (std), 45°/90° hanger, 49" long (plated, FOB TX, 4 week notice) **\$10.29/ea**
- OR**
- HF30 (std, w/ plate), precast 21/4/2 hanger, 90° hanger (FOB TX, 4 week notice, approx 240 req'd) **\$8.24/ea**
- HF42 (HD, w/ plate), precast 21/4/2 hanger, 45° hanger (FOB TX, 4 week notice, approx 240 req'd) **\$9.87/ea**

PLUS TAX

Notice: A charge of 2% of value will be assessed if forms are not returned cleaned and oiled. Form plywood faces and steel rails require cleaning by brushing with a wire brush or rubbing with a burlap cloth to remove concrete buildup.

STATE SALES TAX: **TO BE PAID BY CONTRACTOR**

We will provide the deliver costs