MARK	SECTION (B x H)	END OF BM	CL NORTH/ WEST SUPPORT	FO SUPPORT	CL SPAN	FO SUPPORT	CL SOUTH/ EAST SUPPORT	END OF BM	REMARKS
B7-01	12"x29 1/2"	#4	2- #6 3- #8 ALL @ 12"						
B7-02	15"x29 1/2"	#4	2- #7 0.33 Ln 1- #9 LAP SPLICE 0.1 Ln, TYP 1- #9 2- #9 BAL @ 9"					CANTILEVERED	
B7-02 CANT	15"x18"	#4	2- #7 + 1- #9 END OF CANTILEVER 2- #9 BAL @ 6"						
B7-03	16"x34"	#4	2- #8 0.33 Ln 1- #8 1- #8 0.1 Ln, TYP 2- #8 BAL @ 12"					CANTILEVERED	
B7-03 CANT	16"x34"	#4	2- #8 1- #8 2- #8 BAL @ 9"						
B7-04	10"x60"	#4	2- #6 2- #6 2"		BAL@12"		2"		
B7-05	10"x60"	#4	2- #10 2- #9 2" 6@9"		BAL@12"	6@9"	2"		
B6-01	18"x37"	4"	END OF CANTILEVER 2" BAL@9"	2"	4- #11 3- #11 BAL@9"		2"	#5	
B6-02	24"x37"	4"	END OF CANTILEVER 2" BAL@6"	2"	6- #11 4- #11 BAL@6"		2"	#5	



1 BEAM AXIS ORIENTATION

NOTES:
1. ld = DEVELOPMENT LENGTH

*REFER TO S-610 FOR DETAILS

NUMBER	DATE	DESCRIPTION
01	05/07/2015	Addendum 02
02	08/06/2015	Addendum 03
03	10/30/2015	Addendum 04
04	05/27/2016	Addendum 05

hla
howard laks architects
1545 twelfth street
santa monica, ca 90401
voice : 310-393-4455
fax : 310-393-2230

CONSULTANTS

saiful bouquet structural engineers
136 S. Lake Avenue
Pasadena, California 91101
Telephone 626-304-3616
Facsimile 626-304-3626
SB Job No: 13482

710 WILSHIRE BOULEVARD

MIXED-USE HOTEL PROJECT
SANTA MONICA - CALIFORNIA, 90401

6TH AND 7TH FLOOR CONCRETE BEAM SCHEDULE

REGISTERED PROFESSIONAL ENGINEER
SAIFUL BOUQUET
C 46401
EXP. 09/30/16
STRUCTURAL
STATE OF CALIFORNIA

DETAIL: –
CHECK: ED
APPR: MD
SCALE: 1/8" = 1'-0"
SHEET: S-614
DATE: June 25, 2013
PROJECT NUMBER: HLA 0000000-00000